

32-32-29W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company. SINCIAIR OIL & GAS CO.
Farm- Stevens No. 1

SEC. 32 T. 32 R. 29W
C NW NW

Total Depth. 5815'
Comm. 5-13-60 Comp. 6-12-60
Shot or Treated.
Contractor. Garvey Drlg. Co.
Issued. 4-22-61

County Meade
KANSAS



CASING:
13 3/8" 64' cem w/75 sx.
8 5/8" 1568' cem w/900 sx.
4 1/2" 5814' cem w/250 sx.

Elevation. 2703'

Production. 96 BOPD &
6,729,000 CFG

Figures Indicate Bottom of Formations.

surface soil & sand	64
sand & shale	495
red bed, lime w/sand strks	900
red bed & sand	998
sand	1245
shale & anhydrite	1415
red bed & shale	1465
Anhydrite	1505
red bed & gyp	1570
Anhydrite & red bed	1645
red bed w/anhydrite strks	1915
shale & anhydrite strks	2470
lime & shale	2720
lime	3045
lime & shale	3110
lime & shale w/chert	3170
lime & shale w/chalk	3240
lime & shale	3305
chalky lime & shale	3588
lime & shale	4290
shale & lime	4437
lime & shale	4550
lime	4577
lime w/chert streaks	4630
lime w/chalk streaks	4692
lime w/shale streaks	4757
lime	5273
lime & shale	5484
lime	5522
lime & chert	5545
lime & shale	5592
lime	5628
shale, lime & sand	5716
lime	5743
lime & shale	5804
lime	5815
Total Depth	

TOPS: SCOUT

Heebner	4379
Lansing	4557
Marmaton	5161
Morrow	5592
Morrow Sand	5641
Mississippi Chert	5702
Mississippi	5850