


1-154W MAP NO. _____ REPL. COMP. SEC. 19-32S-29W
 STATE Kans COUNTY Meade App. LOC C SE SW
 OPER. Continental Oil Co. 660 FT/FR S LINE
 WELL 1 FARM Earl Utz 1980 FT/FR W LINE
Angell ELEV. GR. 2721 DF 2724 KB
 CONT. Capitt tools, Rig #6 GEOL. Jim Duvlin
 CO. _____
 INT. _____
 F.R. 11-30-60 SPUD 12-1-60 COMP. 1-13-61
 TD. 5735 FM. Chester PBTD. 5703

COMP.
RECORD

D&A
 8" @1675/800 sx. - 4½" @5734/200 sx.
 (DF Sp1) (DF Log)



Data Inc.

Lans	4522	-1801	Chero	5314	-2593
Marm	5117	-2396	Atoka	5514	-2793
Chero	5320		Morr	5590	-2869
RTD	3735		Chest	5660	-2939

RTD 3735 (Chest) Log, 4½" 5734/200 sx., No DST's, CO 5703
 PBTD (top cem) GRN Log, Perf 12/5592-96, 12/5600-05, 12/5610-
 20, 500 MA all perfs, § 1d + SO & VSSG/NT, Frac (30,000# sd x
 30,000A), § & flo 1d + est 264 Mcfgpd, R 1d, Hooked up, Ga
 317 Mcfgpd thru 3/4" choke, Produced 100 Mcfg per month +

lots SW, FTP 0#, FCP 275#/SW disposal cost too high, Well
 Plugged in Feb 1963 D&A COMPLETED

REPLACEMENT COMPLETION: (3-5-63)

CORRECTION: Replaced with additional information 2-21-63

LIBERAL TOPS

2724 KB

Heebner 4374 (-1650)

Lansing 4510 (-1786)

Marmaton 5140 (-2416)

Morrow 5586 (-2862)

"S-2" Sand 5590 (-2866) 14/18; \$ SS0&G, est 264 MCF

Chester 5662 (-2938)

TD 5735