



State Geological Survey

KANSAS DRILLERS LOG

WICHITA BRANCH

API No. 15 — 191 — 21,244
County Number

Operator

Hummon Corporation

Address

400 One Main Place, Wichita, KS.

Well No.

#5

Lease Name

Hartman

Footage Location

330

feet from (N) (E) line

840

feet from (E) (W) line

Principal Contractor

Aspen Oil, Inc.

Geologist

Steve Miller

Spud Date

3/26/81

Total Depth

3362½

P.B.T.D.

Date Completed

4/22/81

Oil Purchaser

Clear Creek


S. 30 T. 32 R. 3 ^{xxx}E
W

Loc. 150' E/ NE NW NW

County Sumner

640 Acres

N



Locate well correctly

Elev.: Gr. 1199

DF 1201 KB 1204

CASING RECORD

Report of all strings set— surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs./ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface		8 5/8	24#	195	Common	175	2% gel 3%cc
Production		4½	10.5	3350	60-40 Poz	125	18% salt, 3/4 of 1% CFR2.

LINER RECORD

Top, ft.	Bottom, ft.	Sacks cement

PERFORATION RECORD

Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at
2 3/8"	3358	

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production	Producing method (flowing, pumping, gas lift, etc.)
4-22-81	pumping

RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	60 bbls.	MCF	20 bbls.	CFPB

Disposition of gas (vented, used on lease or sold)	Producing interval (s)
	open

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Hummon Corporation		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: oil																	
Well No. #5	Lease Name Hartman																		
S <u>30</u> T <u>32</u> R <u>3</u> ^{EX} _W																			
WELL LOG Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.																	
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th style="padding: 5px; text-align: center;">NAME</th> <th style="padding: 5px; text-align: center;">DEPTH</th> </tr> </thead> <tbody> <tr> <td colspan="2" style="padding: 5px;"><u>Sample tops</u></td> </tr> <tr> <td style="padding: 5px;">IC Sd</td> <td style="padding: 5px;">1621 -417</td> </tr> <tr> <td style="padding: 5px;">Wab</td> <td style="padding: 5px;">1650 -446</td> </tr> <tr> <td style="padding: 5px;">Heebner</td> <td style="padding: 5px;">2606 -1405</td> </tr> <tr> <td style="padding: 5px;">Iatan Lm</td> <td style="padding: 5px;">2930 -1729</td> </tr> <tr> <td style="padding: 5px;">KC</td> <td style="padding: 5px;">3240 -2039</td> </tr> <tr> <td style="padding: 5px;">RTD 3354</td> <td></td> </tr> </tbody> </table>	NAME	DEPTH	<u>Sample tops</u>		IC Sd	1621 -417	Wab	1650 -446	Heebner	2606 -1405	Iatan Lm	2930 -1729	KC	3240 -2039	RTD 3354	
NAME	DEPTH																		
<u>Sample tops</u>																			
IC Sd	1621 -417																		
Wab	1650 -446																		
Heebner	2606 -1405																		
Iatan Lm	2930 -1729																		
KC	3240 -2039																		
RTD 3354																			
DST #1: 3247-60 OP 30-45-30-45 Rec. 1500' GIP 45' SO&GCM 180' HOGM DST #2: 3341-3354 GTS final SI OP 30-45-30-45 Strong blow Rec. 90' OCM 210' Frothy oil	Strong blow SIP 1003-984 FP 28-67 SIP 1203-1203 FP 48-77																		
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.																			
Date Received	 Signature Wilber Berg Title Date																		