


KANSAS

WICHITA BRANCH
WELL COMPLETION REPORT AND
DRILLER'S LOGAPI No. 15 — Sumner — 15-191-20,972
County NumberS. 30 T. 32 R. 3 W

Loc. 15' E of NE SE NW

County Sumner

640 Acres
N

Elev.: Gr. 1190'

DF KB 1195'

Operator TOMLINSON OIL CO., INC.			
Address 200 W. Douglas Suite 1030 Wichita, KS. 67202			
Well No. #1-A	Lease Name Ohnemiller		
Footage Location 990 feet from (N) (S) line 315 feet from (E) (W) line of NW 1/4			
Principal Contractor Gabbert-Jones		Geologist J. Corry Tinsmon	
Spud Date 10-22-79	Date Completed 11-10-79	Total Depth 3418'	P.B.T.D.
Directional Deviation		Oil and/or Gas Purchaser Koch	

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/2	8 5/8	24#	201'	Common	175	2% gel 3% CC
Production	7 7/8	5 1/2	14#	3409'	60/40 SS Poz.	125	10% salt

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			3	DP Jets	3349'-3353'

Size	Setting depth	Packer set at
2 1/2"	3418'	

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
250 gals. MCA	3349'-3353'

INITIAL PRODUCTION

Date of first production 11-09-79		Producing method (flowing, pumping, gas lift, etc.) Swab	
RATE OF PRODUCTION PER 24 HOURS	Oil 312 bbls.	Gas MCF	Water 168 bbls.
Disposition of gas (vented, used on lease or sold)		Gas-oil ratio CFPB	
		Producing interval(s) 3349'-3353'	

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

operator

TOMLINSON OIL CO., INC.

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:
Oil

Well No.

1-A

Lease Name

Ohnemiller

S 30 T 32 R 3 W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Core #1	3244	3258	<u>SAMPLE TOPS</u>	
Core #2	3345	3370	Cottonwood	1282 (-87)
			B/Admire	1595 (-400)
			Elmont	1860 (-665)
			White Cloud	2027 (-832)
			Iatan	2929 (-1734)
			Stalnaker	3012 (-1817)
			Kansas City	3237 (-2042)
			Drum LS	3349 (-2154)
			TD	3418
D.S.T. - NONE				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Christy Marcia

Signature

Geological Secretary

Title

11-16-79

Date