

KANSAS

WELL COMPLETION REPORT AND  
DRILLER'S LOG

State Geological Survey  
WICHITA BRANCH

API No. 15 — 191 — 21,306  
County Number

S. 32 T. 32 R. 3 <sup>XX</sup>W  
Loc. 2310' FNL & 2310' FWL  
County Sumner County

Operator  
TXO Production Corp.

Address  
200 W. Douglas, Ste. 300, Wichita, KS 67202


Well No. #1 Lease Name Holt "A"

Footage Location  
2310 feet from (N) (S) line 2310 feet from (E) (W) line

Principal Contractor Reynolds Geologist Core Lab

Spud Date 7-9-81 Date Completed 7-28-81 Total Depth 3150' P.B.T.D. 3095'

Directional Deviation Not directionally drilled Oil and/or Gas Purchaser Delhi



Locate well correctly  
Elev.: Gr. 1218  
DF. KB 1226

CASING RECORD

Report of all strings set— surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface		8-5/8"	24#	200'		250	
Production		4-1/2"	10.5#	3126'		200	10% NaCl 8# qil/sxs

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
N/A	N/A	N/A	2 JSPF (7 h.)	Stalnaker	3006-09'

TUBING RECORD

Size	Setting depth	Pecker set at
2-3/8"	2986	2955

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Dumped 250 gals acetic acid & loaded hole w/42 bbls 2% KCl wtr	

INITIAL PRODUCTION

Date of first production 9-15-81	Producing method (flowing, pumping, gas lift, etc.) flowing
RATE OF PRODUCTION PER 24 HOURS	Oil N/A bbls. Gas 790 MCFD MCF Water no fluid bbls. Gas-oil ratio N/A CFPB
Disposition of gas (vented, used on lease or sold) sold	Producing interval (s) 3006-09

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be trans-  
mitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation  
Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note  
Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

FIELD: Jordan Creek (Stalnaker)

Operator TXO Production Corp.		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: gas
Well No. #1	Lease Name Holt "A"	
S 32 T 32S R 3 <sup>W</sup> <sub>W</sub>		

**WELL LOG**

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
LOG TOPS				
Heebner	2660	-1434		
Douglas Grp.	2776	-1550		
Iatan	2984	-1758		
Stalnaker	3005	-1779		
RTD	3150			
LTD	3139			
PBD	3095			
Ran O.H. Logs				
DST #1, 3001-31' (Stalnaker), w/results as follows: Weak blow 1st opening, died in 5", no blow 2nd opening POOH Left bottom half of lower pkr & 30' perf anchor in hole. Tool improperly made up or worn up.				
DST #2, 3001-31' (Stalnaker), w/results as follows: Pkr failure, misrun.				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	 Signature
	Harold R. Trapp District Geologist Title
	September 17, 1981 Date