

This form shall be filed in duplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within ten days after the completion of the well, regardless of how the well was completed.

Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on side one will be of public record and side two will then be held confidential.

Circle one: Oil, Gas, Dry, SWD, OWWO, Injection. Type and complete ALL sections.

Applications must be filed for dual completion, commingling, SWD and injection, T.A.

Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.).

KCC # (316) 263-3238. (Rules 82-2-105 & 82-2-125)

OPERATOR Hummon Corporation

API NO. 191-21,348

ADDRESS 400 One Main Place

COUNTY Sumner

Wichita, KS 67202

FIELD _____

**CONTACT PERSON Wilber Berg

PROD. FORMATION _____

PHONE 263-8521

LEASE Hartman

PURCHASER _____

WELL NO. 9

ADDRESS _____

WELL LOCATION NE SW SW

DRILLING CONTRACTOR Big-H Drilling, Inc.

990 Ft. from South Line and

ADDRESS 400 One Main Place

990 Ft. from West Line of

Wichita, KS 67202

the SW/4 SEC. 19 TWP. 32S RGE. 8W


WELL PLAT

3W

PLUGGING CONTRACTOR Big-H Drilling, Inc.

ADDRESS 400 One Main Place

Wichita, KS 67202



KCC _____
KGS _____
(Office Use)

TOTAL DEPTH 4361 PBTD _____

SPUD DATE 1-8-82 DATE COMPLETED 1-27-82

ELEV: GR 1205 DF 1203 KB 1292

DRILLED WITH (CABLE) (ROTARY) (AIR) TOOLS

Amount of surface pipe set and cemented 8-5/8" @ 210'. DV Tool Used? _____

A F F I D A V I T

STATE OF Kansas, COUNTY OF Sedgwick SS, I, _____

Wilber Berg OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS OATH,

DEPOSES THAT HE IS Production Manager (FOR)(OF) Hummon Corporation

OPERATOR OF THE Hartman LEASE, AND IS DULY AUTHORIZED TO MAKE

THIS AFFIDAVIT FOR AND ON THE BEHALF OF SAID OPERATOR, THAT WELL NO. 9 ON

SAID LEASE HAS BEEN COMPLETED AS OF THE 27 DAY OF January, 19 82, AND THAT

ALL INFORMATION ENTERED HEREIN WITH RESPECT TO SAID WELL IS TRUE AND CORRECT

SIDE TWO

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
			<u>LOG TOPS</u>	
DST #1: 2033-2055' OP 15/30/15/30 No blow, valve on 2" line frozen shut Rec. 62' GCM 186' G&WCM 124' G&MCW	FP 31-115, 73-157 SIP 742-742 HP 1054-1012		Ind Cv Sd Stn Wabanssee White Cloud Heebner Kansas City Mississippi Kinderhook Sh Simpson Sd LTD 4364	1625 - 420 1653 - 448 2040 - 835 2617 -1412 3255 -2050 3915 -2710 4268 -3063 4360 -3155
DST #2: 3359-3375' OP 45/60/45/60 Rec. 30' WC&VSOCM 240' WM	FP 30-100, 101-171 SIP 1168-1168 HP 1612-1753			
DST #3: 3915-3930' OP 30/60/30/60 Strong blow on both op GTS @ end of 2nd SI, too small to measure Rec. 130' Mud.	FP 40-50, 40-70 SIP 1531-1531 HP 2026-2026			
DST #4: 4345-4361' OP 45/60/45/60 Wk-bldg. to fair blow on both openings Rec. 62' OGCM 62' GCM 62' GCW	FP 40-90, 70-121 SIP 1804-1804 HP 2260-2209		Clay & Shale Red beds & Sh Shale & Lime Lime & Shale Lm & Sh & Clay Shale Lime K.C. Lime & Shale Lime Lime & Shale Mississippi Lime Lime & Shale Shale & Lime Sand Stone	210-560 560-1064 2064-2140 2140-2864 2864-3072 3072-3318 3318-3375 3375-3395 3395-3455 3455-3542 3542-3930 3930-3934 3934-4008 4008-4243 4243-4357 4357-RTD

State Geological Survey
WICHITA, BRANCH

Report of all strings set — surface, intermediate, production, etc. CASING RECORD (New) or (Used)

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface		8-5/8"	20#	210'	Common	150	2% gel, 3% CC

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD		
Size	Setting depth	Packer set at

*NOTE: Correction on spot location.

HUMMON CORPORATION - DAILY WELL REPORT

State Geological Survey
WICHITA, BRANCH

LEASE #9 Hartman PROSPECT Hartman/79 ELEVATION 1205 KB 1203 DF 1292 Gr.
 SPOT NE SW SW SECTION 19-32S-~~SW~~ 3W TOPS: SAMPLE ELECT. LOG
 COUNTY Sumner STATE Kansas Ind Cv Sd Stn 1627 - 422 1625 - 420
 Wabensee 1658 - 453 1653 - 448
 White Cloud 2042 - 837 2040 - 835
 Heebner 2617 -1412 2617 -1412
 Toronto 2632 -1427
 Iatan Lm 2944 -1739
 Stalnaker Sd 2954 -1749
 Top K.C. 3254 -2049 3255 -2050
 Miss. 3912 -2707 3915 -2710
 Kinderhook Sh 4266 -3061 4268 -3063
 Simpson Sd 4357 -3152 4360 -3155
 RTD 4361 LTD 4364

CONTRACTOR Big-H Drilling, Inc.
 GEOLOGIST Tim Pierce
 MIRT 1-15-82 (Big-H) SPD
 Harp Well & Pump Service MICT & RU. Spd. 12:15
 pm, 1-8-82, Set new 20#, 8-5/8" surf. csg. @ 210'
 w/150 sx Common, 2% gel, 3% CC. PD 4:30 pm.

DATE	REPORT	
1-15-82	Big-H MIRT and commence drilling.	
1-16-82	Drlg. @ 1064' Vis 30, MW 9.8	CMC \$ 396.55
1-17-82	Drlg. @ 1840' Vis 32, MW 9.7	CMC \$ 396.55

DST #1: 2033-2055'
 OP 15/30/15/30 FP 31-115, 73-157
 No blow, valve on 2" SIP 742-742
 line frozen shut HP 1054-1012
 Rec. 62' GCM
 186' G&WCM
 124' G&MCW

1-18-82	Drlg. @ 2140' Vis 32, MW 9.8	CMC \$ 643.03
1-19-82	Drlg. @ 2700' Vis 32, MW 9.5	CMC \$1,970.43
1-20-82	Drlg. @ 3218' Vis 38, MW 9.5	CMC \$3,891.18

DST #2: 3359-3375'
 OP 45/60/45/60 FP 30-100, 101-171
 Rec. 30' WC&VSOCM SIP 1168-1168
 240' WM HP 1612-1753

1-21-82	Drlg. @ 3375' Vis 41, MW 9.5, WL 15	CMC \$4,480.99
1-22-82	Drlg. @ 3630' Vis 36, MW 9.4, WL 20	CMC \$4,930.09
1-23-82	@ 3930' Vis 38, MW 9.4,	CMC \$6,117.54

DST #3: 3915-3930'
 OP 30/60/30/60 FP 40-50, 40-70
 Strong blow on both op. SIP 1531-1531
 GTS @ end of 2nd SI, HP 2026-2026
 too small to measure
 Rec. 130' mud.

1-24-82	Drlg. @ 4008' Vis 38, MW 9.6, WL 10.8	CMC \$ 6,398.54
1-25-82	Drlg. @ 4293' Vis 40, MW 9.6, WL 11	CMC \$ 7,405.22
1-26-82	@ 4361' Vis 46, MW 9.6, WL 16	CMC \$ 8,366.54

DST #4: 4345-4361'
 OP 45/60/45/60 FP 40-90, 70-121
 Weak-bldg. to fair blow SIP 1804-1804
 on both openings HP 2260-2209
 Rec. 62' OGCM
 62' GCM
 62' GCW

1-27-82 P&A
 Plugged w/60 sx @ 540', 40 sx @ 210', 10 sx @ 40', 10 sx in rathole, 10 sx in mousehole. Job complete 5:00 am. St. Plugger Maurice Leslie @ Nashville, KS.

RECEIVED
 STATE CORPORATION

FEB - 4 1982

CONSERVATION DIVISION
 Wichita, Kansas