

KANSAS GEOLOGICAL SOCIETY  
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU  
 KANSAS GEOLOGICAL SOCIETY BUILDING  
 508 EAST MURDOCK - WICHITA, KANSAS

4-32-30W

COMPANY CLEARY PETROLEUM, INC.

SEC. 7 T. 32 R. 30W

FARM Mitchell NO. 1

LOC. C SE NW

TOTAL DEPTH 6150

COUNTY Meade


COMM. 6-4-68

COMP. 6-23-68

SHOT OR TREATED

CONTRACTOR Rine Drlg.

ISSUED 8-31-68



CASING

|    |        |                  |
|----|--------|------------------|
| 20 | 10     |                  |
| 15 | 8 5/8" | @ 1710' w/700 sx |
| 12 | 6      |                  |
| 13 | 5      |                  |

ELEVATION 2784' KB

PRODUCTION DRY/SPEC

MITCHELL WELL NO. 1

FIGURES INDICATE BOTTOM OF FORMATIONS

MEADE COUNTY, KANSAS

CONTRACTOR: RINE DRILLING COMPANY, INC.

STARTED: JUNE 4, 1968

COMPLETED: JUNE 23, 1968

LOG

|                     |       |   |       |
|---------------------|-------|---|-------|
| Sand & Clay         | 0'    | - | 1370' |
| Red Bed & Anhydrite | 1370' | - | 2310' |
| <br>                |       |   |       |
| Anhydrite & Shale   | 2310' | - | 2915' |
| Lime                | 2915' | - | 3714' |
| Lime & Chalk        | 3714' | - | 4034' |
| Lime                | 4034' | - | 4158' |
| Lime & Chalk        | 4158' | - | 4357' |
| Lime                | 4357' | - | 5510' |
| Lime & Shale        | 5510' | - | 5560' |
| Lime                | 5560' | - | 6150' |

Totco - 1/4" @ 190'  
 Ran total 60 jts. 8 5/8 2 jts. 8rd.  
 24# on bottom 57 jts. 32# 10rd. 1jts  
 24 8rd. 10rd. set @ 1710' cem. w/20  
 sx. reg. 2% cc 700 sx. Poz 2% cc 2  
 gel.

Totco - 3/4" @ 2639'

T.D.-Plug w/35 sx. reg. @ 900'. Plu  
 w/15 sx. @ 45.

STATE OF KANSAS )  
 COUNTY OF SEDGWICK)

SS

|  |              |      |
|--|--------------|------|
|  | TOPS: SAMPLE |      |
|  | Heebner      | 4272 |
|  | Toronto      | 4316 |
|  | Lansing      | 4423 |
|  | Marmaton     | 5034 |
|  | Cherokee     | 5185 |
|  | Morrow       | 5480 |
|  | Chester      | 5546 |
|  | Ste Geneva   | 5728 |
|  | St Louis     | 5812 |
|  | Spargen      | 6045 |

