

17-32-30W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- COOP. REFG. ASSOC. & EARL F. WAKEFIELD
Farm- Baty No. 1

SEC. 17 T. 32 R. 30W
C SW SW

Total Depth. 5722'
Comm. 6-5-56 Comp. 7-12-56
Shot or Treated.
Contractor. Earl F. Wakefield
Issued. 3-16-57

County Meade
KANSAS



Elevation. 2782' RB.

Production. 7,900,000 CFGPD

CASING:

8 5/8" 1580'
5 1/2" 5721'

Figures indicate Bottom of Formations.

gyp-sand	131
sand-gravel	490
red bed	515
red shale	990
red bed	1070
shale-shells	1170
sand	1300
shale-shells	1526
Anhydrite	1580
Anhydrite-red shale	1635
red shale	2015
shale-lime	2180
shale-shells	2510
shale-lime	2655
shale-shells	2755
shale	2795
shale-lime	3060
lime	3177
lime-shale	3375
lime	3490
lime-shale	3625
chalky lime	3725
lime	3810
lime-shale	3812
lime	3845
chalky lime	3875
lime	3935
lime-shale	4383
lime-brkn	4455
lime-shale	4535
lime	4620
lime-shale	4710
lime	5045
lime-shale	5145
lime	5225
lime-shale	5365
lime	5459
lime-shale	5490
lime-cherty	5508

lime-shale	5593
lime	5610
sand-Morrow	5636
cherty lime	5670
lime	5722
Total Depth	
TOPS: Scout	
Heebner	4388
Lansing	4517
B/Kansas City	5063
Marmaton	5119
Cherokee	5277
Morrow sand	5598