


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- CHAMPLIN OIL & REFINING CO.
Farm- Herman C. Bender No. 1

SEC. 33 T. 32 R. 30W
C SW NE

Total Depth. 5750'
Comm. 4-1-57 Comp. 4-12-57
Shot or Treated.
Contractor. Earl Wakefield
Issued. 7-4-59

County Meade
KANSAS



CASING:
8" 1813'

Elevation. 2752'

Production. Dry

Figures Indicate Bottom of Formations.

surface soil & sand	125
sand & shale	750
red bed & lime shells	991
red bed - lime strks	1356
shale & lime strks	1510
Anhydrite	1650
shale & anhydrite	1805
shale & red bed	1998
shale, dolomite & anhydrite	2312
shale & lime	2709
lime & chert strks	2747
sandy lime, shale, anhydrite	2869
shale, strks of anhydrite	2915
lime & shale	3019
lime, shale & chalky lime	3106
chalky lime, strks chert	3135
lime, shale, strks chalky	
lime	3418
chalky lime	3600
lime	3610
shale & lime	3674
shale & chalky lime	3961
lime, shale, chert	4006
Marbelized lime & chert	4046
lime & chert	4060
lime, shale, strks of chalky	
lime	4150
lime & shale	4214
black shale	4300
lime & shale	4445
chalky lime & shale	4500
lime & shale	4515
lime	4564
chalky lime & shale	4615
lime & shale	4923
lime	4940
shale	4965
chalk & shale	5014
chalky lime & shale	5053
lime & shale	5394
shale, strks lime	5463
lime & shale	5573
lime & shale - sand	5597
shale	5640
shale & sand	5672
shale	5702
shale & lime	5750
Total Depth	

DST #1 5583-97', op 2 hrs, weak blow 5 mins and died, rec. 30' drlg. mud, IFP 0#, FFP 0#, ISIP 0#/20", FSIP 0#/20", preparing to drill ahead.

DST #2 5583-5672', op 2 hrs, gas to surf. in 1 hr & 55 mins., too small to measure, rec. 300' gas cut mud, IFP 240#, FFP 275#, ISIP 2215#/30", FSIP 310#/30".

TOPS:
Lansing-Kansas City 4500
Base Kansas City 5067
Marmaton 5131
Cherokee 5296
Base Cherokee Atoka Sand 5587-90
Morrow 5592
Morrow Sand 5608-30
Mississippi (Chester) 5658