

33-32-30W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
50S East Murdock, Wichita, Kansas

Company- PHILLIPS PETRO. CO.
Farm- Herman "A" No. 1

SEC. 33 T. 32 R. 30W
C NW NW
660' FNL 657' FWL NW

Total Depth. 5721' PB 5668'
Comm. 11-19-56 Comp. 12-18-56
Shot or Treated.
Contractor.
Issued. 6-8-57

County Meade
KANSAS



CASING:
8 5/8" 1804' 2 / 875 sx cem.
5 1/2" 5699.76' w/75 sx cem.

Elevation. 2754 DF

Production. 2,700,000 CFG

Figures indicate Bottom of Formations.

Anhydrite	1900
anhydrite-dolomite	2721
Dolomite	3015
lime-shale	4275
lime	5517
sand	5600
lime	5720 RTD
lime	5721
Total Depth PB 5668	

TOPS: Electric.	
Hollenberg	2650
Herington	2705
Winfield	2762
Ft. Riley	2883
B. Florence	2974
Wreford	3038
Coun. Grove Grp.	3079
Neva	3268
Waba unsee Grp.	3478
Ta rkio	3586
Elmont	3630
Howard	3910
Topeka	3984
Lecompton	4168
Heebner	4351
Toronto	4369
Douglas	4402
Lansing-Kansas City	4474
Drum	4723
B/Kansas City	5035
Marmaton	5072
Cherokee	5270
Keyes sand	5572
Mississippian-Chester	5621

DST #2 - packer sea t failed.
DST #3 - 5573-5600, open 30 mins., rec. 5,002,000, rec. 100' G CM. BHP 1,680# 20 mins., IFP 430#-679#.

DST #4 - 5621-70, open 1 hr., rec. 30' mud. LWP & FWP zero. B HP 20# in 20 mins. Plug back T.D. 5668'.

Perf. 96 \$ 5574-5590, 500 mud acid. Well kicked off and completed for the above. Well produced 85 gals. distillate in 8 hrs. Producing formation Morrow.

DST #1 - 5573-5600; failed to rupture disc. B HP 1,750#.

