

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

33-32-30W


Company- ALADDIN PETROLEUM CORP.
 Farm- Vail No. 1

SEC. 33 T. 32 R.30W
 SE SE SE

Total Depth. 5744'
 Comm. 10-5-55 Comp. 12-12-55
 Shot or Treated.
 Contractor. Dutch George Drlg. Co.
 Issued. 3-31-56

County Meade

KANSAS



Elevation. 2743' KB

Production. 47,250,000 MCF/PD

CASING:
 13 3/8" 636' cem w/600 sx
 8 5/8" 2706' cem w/1600 sx
 5 1/2" 5744' cem w/300 sx

Figures indicate Bottom of Formations.

red beds and sand	126	lime	5089
red beds	434	lime and shale	5165
red beds and shells	620	lime	5240
red beds and shale	636	lime and shale	5285
lime and shells	645	lime	5350
red beds	840	lime and shale	5485
red beds and chalk	1060	lime	5513
sand	1165	lime and shale	5581
red beds and sand	1225	coring	5633
red beds and shells	1490	sand	5678
shale and lime strks	1595	lime	5735
lime and red beds	1715	lime	5744
lime	1820	Total Depth	
lime and red beds	1910		
lime	2050		
lime and shale	2135	Tops:	
lime	2195	Lansing	4497
lime and shale	2340	Marmaton Limestone	5117
lime	2355	Atoka	5373
lime and shale	2450	Morrow	5570
lime	2485		
lime and red shale	2520	Perforated 40 holes from 5596' to 5606'	
lime	2570	72 holes from 5612' to 5630'	
lime - cherty	2586		
lime	2660		
anhydrite and lime	2670		
lime & shale	2755		
lime sand & shale	2910		
lime	3155		
lime & shale	3233		
lime	3280		
lime and shale	3320		
sandy shale	3385		
sandy lime & shale	3565		
lime	3585		
lime and shale	3715		
sandy shale	3790		
chalky lime	3830		
lime	3903		
shale & lime strks	4075		
lime	4095		
black shale	4120		
shale and lime	4140		
lime	4196		
lime and shale	4310		
chalky lime	4340		
sandy shale and lime	4410		
lime	4488		
lime and shale	4515		
sandy lime	4589		
lime and chalk	4643		
lime	4713		
sandy lime	4745		
chalky lime	4790		
lime	4911		
lime and shale	4955		
Porous lime	4999		
lime and shale	5040		