


State KANSAS Field Leslie
 Company CARTER Oil Co County Wade
 Farm BEHNKE - YALL No. 1
 Sec. 34 Twp. 32 Range 30

Spot NE SW SW



Contractor WALTER BEARDSHAW

Remarks SUNNY 50% 5700' PD

Comm. 8/22/56 Comp. 10/17/56
 Elev. DF 2747 GL 2738 KB TD 5800 PB 5685
 Pay 5619-23 5628-32 5651-58

P&A 2/8/59
 I.P. COF. 1,266 MCF Press. 51CP 650
 Casing Record: 13 3/8 7"
 20" 10 3/4 5 1/2" 5797/250
 16" 8 5/8 1546/900

Voc	Sample	Log
AUG 15 MIE	Cottonwood 3190	Wing 2776
AUG 22 R.U.T.	TOR 4380	FTBil 2838
AUG 29 8 1/8 1546/900	Lane 4520	TOR 4386
2914	Nodges 4954	Lane 4506
SEP 5 4310 sh + lm.	Marm 5124	Hodge 4950
SEP 12 TTD 5618 circ	Cck 5336	Marm 5101
SEP 19 DST # 1 5656-85 up 1 hr.	Mon fm 5609	Cck 5300
wk bla died rec 15' mud	Chst 5694	Mon fm 5604
FPO BHP 0/30		Ad 5620
RTD 5800 Nam schl 5800		Chst 5694
DST # 2 (SP) 5585-5624 up	1 1/2 hrs f to gd	blo - dr to fr
in 1 hr. rec 30' mud FP 40	BHP 40/30	
DST # 3 (SP) 5619-58 up	1 hr. gd blo. 97S 3 1/2" aft 10"	
g. 1,630 mcf. aft 30" g. 1,860 MCF	TD. Rec. 120'	
gcm. + 60' shi salty gcm. FP 315	BHP 1765/30	
set 5 1/2 @ 5797/250	PBTD 5761	SUCT.
SEP 28 RUCT Lan G.R. p 72/5701-13	132/5719-41	
Namt to 5716 w/pl @ 5684	A/1000 m. 5 li'	
sho gas A/3000 . g 196 MCF	pulled T & P.	
from 20,000 Ad/10,000	Kero/168 total.	
Namt w/pl. 10HR BD. g 2,530 MCF		
+ load 24hr BD 1,630 MCF + load		
FTP 754		

OCT 3 - 24hr BD 734 MCF. ~~from~~ + load. 4R. SW
FTP 204 from 10,000 sd/10,000. Swt + load
pulled T & Pk PPTD 5685 at 24/5619-23
24/5628-32 28/5651-58 from Tub.

OCT 10 A/1000 Knp/10,000 sd/10,000 2" T to 5620
switched + flowed 209 bbl oil 1/2" ck FTP
300 FCP 475 gas = 3,000 MCF. - 2 1/2 hrs
flowed 2 bbl load of 1,000 MCF FTP 150
FCP 300 seeps 85 51 2 1/2 hrs
SITP 610 SITP 650

OCT 17 1pt BDT 24hr BD 4,200 MCF + TR H₂O 1/2" ck
FTP 150, FCP 300, cal of 1,266 MCF, SITP 610,
SICP 650

φ

P & A 12/8/59

AMARILLO TOPS

2747 DF

Winfield 2774 (-27)

Heebner 4370 (-1628)

Lansing 4505 (-1758)

Morrow 5604 (-2857)

Morrow Sand 5620 (-2873) T 14', por 4', G COF 1,266 MCF

Chester 5694 (-2947)

TD 5800 (-3053)