


State KANSAS Field Leslie
Company C O G County Meade
Farm Holmes No. 9
Sec. 35 Twp. 32S Range 30W

Spot C SE SW

Contractor NYE & SNEII

Remarks 5900 PD



Comm. 8/12/56 Comp. 11-7-56

Elev. DF 2735 GL 2727 KB TD 5810 PB

Pay 5750-54

5713-43

I.P. 14,121 MCF Press. 51CP 1370
51TP 1370

Casing Record: 13 3/8 7"

20" 10 3/4 5 1/2" 5797/200

16" 8 5/8 1622/100

Sample	Log
41591	
Aug 22 870" @ 1622/100	Lane 4526
5662	Mamm 5138
AUG 29 5667-92 N 25'	CE 5300
5' grey shly. low sh. oolite	Atoka 5444
10' bl. sh.	MOR 5605
10' grey fine tite. low.	Miss 5668
5692-5718 sec 26'	
1 1/2' sh. bl.	
2 1/2' sh. grey v. fine.	
3 1/2' sh. bl.	
1' grey fine low sh. oolite	
1' sh. bl.	
4 1/2' low. as above bleed oil	
1' sh. grey to tan. low. cong.	
6' tan to grey v. fine low.	
very poor sh. bleed oil	
1' sh. grey	
2' low tan to grey v. fine shly. bl. tite (NS)	
1' grey sh.	
5719	
SEP 12 RTD 5810 low log MICT Co to ?	
16/5750-54 120/5713-43 A/1000 m	

subbed NS A/3000 frac/3000 + frac/3000
sd/1500 A/1000 subbed load KO sli
sho gas sho vs oil g 6,000 MCF + oil spray
lat g 7,000 + 80 bbls fluid per day 16% Acid
water.

SEP 19 - frac/20000 sd/10,000 g 18,300 MCF. spray
of oily water gr. 34" lat g. 16,000 + fluid (oil wat.
g 14,200 MCF + fluid in 2" T to 5721 -

SI WOT

SEP 26 ✓ OCT 3 g 2,200 MCF + 15-20 bbls

dit per day.

OCT 10 ✓

OCT 17 ✓

OCT 24

OCT 31 ✓

NOV 20 OP F/6 19,121 MCF

SI CP 1370

SITP 1370

AMARILLO TOPS

2727 GL

Winfield 2784 (-60)

Heebner 4390 (-1666)

Douglas 4400 (-1676)

Lansing 4522 (-1798)

Morrow 5630 (-2906)

5626 (-2891)

Sand 5642 (-2918) T 22', por 20', 352 BOPD

Chester 5704 (-2980)

TD 5808 (-3076)