

Field

State KansasCounty MeadeCompany SinclairFarm AngellWell No. 1Sec. 30 Twp. 32SRange 29W

fr N

fr E

fr S

fr W

of C SE SEContractor Barbour Drlg. Co.Remarks PD 6300' TestComm. 6/8/56Comp. 10/17/56Elev. DE 2714 - 64206 T. D. 5780

P. B.

Pay 5688-5703I. P. Flo 21 BOPD

R. P.

Casing Record: 13 3/8 665/650

7

20 10 3/4

5 1/2 5779/25016 8 5/8 2605/200

	MIRT	Tops	
JUN 13	φ 1300'	Hell 2602	
JUN 20	φ 3238	Heeb 4373 - 4374	
JUN 2	DST 2631-81 - op 30"	LKC 4524 - 4532	
	1' mud. - FP 20 BH 20/30	MAN 5188 - 5184	
	NEW φ 4685	Mar - 5581 *	
JUL 3	φ 5558	1st. Adl 5606 *	
JUL 11	φ 5608-38 rec 30'	2nd. Adl 5638 *	
	1' gty fire sd.	Mia 5688 *	
	8' bl sh.		
	4' dk gty sh w ss stringers.		
	6' ssd sh. 60% sh.		
	8' gty v fngt. fire glux shly ss.		
	2' bl sh.		
	1' gty sli pot ss sli stain.		
	DST. 5588-5638 op 2 hrs. but gd bld		
	Rec. 30' sli gcm. FP. 35 BH 415/30		
	φ 5638-71 Rec. 33'		
	23' gty shly ss mud to fngt. gd odor.		
	10' bl sh.		

DST. 5637-70 op 3 hrs. gts 15" 3 hr g
304 mcf. increasing rec 60' 9 cm F-45750
BHP 1848/30

5671-5708 rec 37'
5' bl sh

10' shly ss. fr gr tite. gas odor.

18' buff xlv. ls. apted stain.

1' gry sh.

4' ls. gry fr. tite.

DST 5662-5708 op 3 hrs. gts 15" max
179 mcf. rec 65' 9 cm. FP 50 BH 1850/30

DST 5707-28 op 30" rec 5' mudl.
FP 20 BH 20/30

DST 5730-80 failed

RTO 5780 now sch 5783 net 5 1/2 5779
w-250 WOCT.

JUL 18 RUCT CO to 5744 pf 36/5655-64 est 100 mcf

A/500 m - frac 10,000 kwh ad 20,000 - rubbed

+ flo 114 bbls load in 14 hrs 13 bbls load

24 hrs of 1,000 MCF 1" ck. 218 bbls load
left testing.

7/25 pf 60/5688-5703 sho gas - MCA/500 below.
run TW net @ 5642 say all pfa w 50 sat,
p clm.

AUG 1 - CO to 5744 top 60/5688-5703 slicker you
frac - sub & flowed load flowed
new oil 3 bph no water or fine but
flowed 5860 in 24 hrs gas 109 MCF

AUG 8 2 1/2" TW pk @ 5568 pr-y to frac.

AUG 15 frac 373 bbls crude

flowed 156 bbls load in 13 hrs. of 500 MCF

Aug 22 flow 52 60/24 hrs (fr miss perf)

gas est @ 1,000 MCF, pull thg + pkr, ran

2 1/2" thg, sub & flow 143 bbls load 18 hrs. (1"

ck) later flow 30 bbls load 24 hrs gauge 1,000

MCF (1" ck) (max perf) TP 100", CP 350", flow

26 bbls load 24 hr (1" ck) testing.

Field _____
State _____ County Meade
Company SINCLAIR
Farm ANGELL Well No. #1
Sec. _____ Twp. _____ Range _____
Blk. _____ Survey _____
_____ fr N _____ fr E _____ fr S _____ fr W
of _____
Contractor PAGE #3
Remarks _____
Comm. _____ Comp. _____
Elev. _____ T. D. _____ P. B. _____
Pay _____

I. P. _____ R. P. _____
Casing Record: 13 3/8 _____ 7 _____
20 _____ 10 3/4 _____ 5 1/2 _____
16 _____ 8 5/8 _____

AUG 29	gent 1,000 MCF 20/6008 ck.
	W.O.T.
SEP 5	put 57 Miss 5688-5703 prod 57 BO new oil in 5 days 57 W.O. pipeline.
SEP 12	flowed 21 BOPD & 800 MCF " ck FTP 38# FCP 120#
SEP 19	SI.
SEP 26	✓
OCT 3	✓
OCT 10	✓
OCT 17	✓

P

AMARILLO TOPS

2706 GL

Winfield 2780 (-74)

C. G. 3010 (-304)

Heebner 4396 (-1690)

Douglas 4408 (-1702)

Lansing 4530 (-1824)

Marmaton 5145 (-2439)

Cherokee 5303 (-2597)

Morrow 5592 (-2886)

"S-" Sd 5606 (-2900) T 7', por 4', SSG

"S-2" Sd 5636 (-2930) T 27', por 21', g 1,000 MCF

Miss 5688 (-2982) ϕ 21 BOPD

TD 5783 (-3082)