

17-32-31W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- **MAGNOLIA PETROLEUM CO.**
Farm- **Mabel I. Hatcher No. 1**
Unit

SEC. **17** T. **32** R. **31W**
SW SE NE

Total Depth. **5781'**
Comm. **5-8-58** Comp. **6-3-58**
Shot or Treated.
Contractor. **Graham-Michaelis Drlg.**
Issued. **7-12-58**

County **Seward**
KANSAS



CASING:
8 5/8" 1508' cem w/800 sx.

Elevation. **2798'**

Production. **Dry**

Figures Indicate Bottom of Formations.

| | |
|-------------------------|----------|
| surface clay & sand | 125 |
| sand | 423 |
| sand - red bed | 785 |
| sand - red bed - shells | 1058 |
| shale & sand | 1310 |
| shale & anhydrite | 1509 |
| shale | 1657 |
| shale w/sand | 2135 |
| shale & lime | 2388 |
| lime & shale | 2867 |
| lime | 3147 |
| lime w/shale | 3320 |
| lime | 3610 |
| lime & shale w/chalk | 3772 |
| lime | 3832 |
| lime & shale | 5661 |
| lime | 5741 |
| lime | 5781 RTD |
| Total Depth | |

| | |
|---------------|------|
| TOPS: SCOUT | |
| Herington | 2638 |
| Heebner | 4235 |
| Toronto | 4277 |
| Lansing | 4377 |
| Marmaton | 5018 |
| Cherokee | 5186 |
| Morrow | 5494 |
| Morrow Sand | 5510 |
| Chester | 5574 |
| St. Genevieve | 5732 |