

KANSAS

State Geological Survey
WICHITA, BRANCHWELL COMPLETION REPORT AND
DRILLER'S LOGS. 23 T. 32 R. 31 E
W

Loc. C N2 NE

County Seward

API No. 15 — 175 — 20,412
County Number

Operator

Calvin Exp., Inc.

Address

5680 S. Syracuse Circle #516 Englewood, Colo 80111

Well No.

#1-23

Lease Name

Fieser

Footage Location

660

feet from (N) (S) line

1175

feet from (E) (W) line

Principal Contractor

Search Drilling

Geologist

Paul Gerlach

Spud Date

9/16/79

Date Completed

9/29/79 D&A

Total Depth


5661'

P.B.T.D.

0

Directional Deviation

Oil and/or Gas Purchaser

640 Acres
N

Locate well correctly

Elev.: Gr. 2875'

DF 2792' KB 2795'

CASING RECORD

Report of all strings set—surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"	23#	1575'	Class H	700 150	2% CaCl w/ 1/4# F. 3% CaCl w/ 1/4# F.
Production	7 7/8"	None					

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

RECEIVED
STATE CORPORATION COMMISSION

Date of first production

D & A

Producing method (flowing, pumping, gas lift, etc.)

RATE OF PRODUCTION
PER 24 HOURS

Oil

bbis.

Gas

MCF

Water

NOV 19 1979

bbis.

CFPB

Disposition of gas (vented, used on lease or sold)

Producing interval
CONSERVATION DIVISION
Wichita, Kansas

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Calvin Exploration, Inc.		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No: #1-23	Lease Name Freser	Dry Hole
S <u>23</u> T <u>32</u> R <u>31</u> XX		

WELL LOG			SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.				
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Conductor Casing	0	64	Chase	
Sand	64	284	Heebner	4318
Sand & Red bed	284	788	Lansing	4444
Red Bed	788	1200	Marmaton	5025
Glorietta	1200	1295	Cherokee	5186
Red Bed	1295	2103	Morrow	5562
Red Bed, Lime & Shale	2103	2405	Chester	5592
Lime & Shale	2405	3125	TD	5655
Council Grove	3125	3325		
Lime & Shale	3325	4449	Logs Run:	
Lansing	4449	4691	DIL-SP-GR	
Lime & Shale	4691	5661	FOC-CNL-	
Rotary Total Depth	5661		GR-CAL	

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	Dean R. Calvin Signature Secretary, Calvin Exploration, Inc. Title November 13, 1979 Date
---------------	--

DRILLERS LOG

FIESER #1-23

CASING RECORD:

8-5/8" set at
1575' with 850 sacks
cement

TOTAL DEPTH:

5661'

OPERATOR: Calvin Exploration

CONTRACTOR: Search Drilling Co.

COMMENCED: September 14, 1979

COMPLETED: September 29, 1979

DESCRIPTION:

C NE/4
Sec. 23-32S-31W
Seward Co., KS

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Conductor casing	0	64	
Sand	64	284	
Sand and Red Bed	284	788	
Red Bed	788	1200	
Glorietta	1200	1295	
Red Bed	1295	2103	
Red Bed, Lime and Shale	2103	2405	
Lime and Shale	2405	3125	
Council Grove	3125	3325	
Lime and Shale	3325	4449	
Lansing	4449	4691	
Lime and Shale	4691	5661	
Rotary Total Depth	5661		

COPY

D&A

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SEARCH DRILLING COMPANY

S. K. May
S. K. May

Subscribed and sworn to before me this 2nd day of October, 1979.

My appointment expires:
February 22, 1981

Maxine Dressen
Maxine Dressen Notary Public

