

DEC 26 1970

26-32-31W
SW 100'5g CSW SW

Co-

WHITE SHIELD OIL & GAS CORPORATION

WILLS NO. 26-1 WELL
Seward County, Kansas

Dry/miss

COMMENCED OPERATIONS: 5-1-69
COMPLETED OPERATIONS: 5-17-69

Elev. 2781' KB

DRILLERS LOG

5-1-69	0 - 343	Sand & Clay.
5-2-69	343 - 1569	Sand, Shells, Red Bed & Anhydrite.
5-4-69	1569 - 2411	Shells, Red Bed, Shale & Anhydrite.
5-5-69	2411 - 2707	Shale & Lime.
5-6-69	2707 - 3150	Lime, Dolomite & Sand.
5-7-69	3150 - 3159	Lime & Dolomite.
5-8-69	3159 - 3770	Lime & Shale.
5-9-69	3770 - 4369	Lime.
5-10-69	4369 - 4769	Lime & Shale.
5-11-69	4769 - 4990	Lime and Shale.
5-12-69	4990 - 5135	Lime w/shale strks.
5-13-69	5135 - 5352	Lime and Shale.
5-14-69	5352 - 5725	Lime and Shale.
5-15-69	5725 - 5923	Lime and Shale.
5-16-69	5923 - 6010	Lime and Shale.

CASING RECORD

5-2-69 Ran 36 Jts. of 28# Used 8 5/8" Casing. Set at 1569K.B. Cemented with 800 sacks 50-50 pozmix w/4% Gel. and 2% c.c. and 200 sacks common w/3% c.c.

5-17-69 Plugged with 35 sacks 800'-900' and 15 sacks 45'-0'

Log Tops

LKC 4424
Mamaton 5113
Morrow 5582
Chest. 5774
St Louis 5978