

29-32-31W


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- MUSGROVE PETROLEUM CORP.  
Farm- Collingwood R3. 1

SEC. 28 T. 32 R. 31W  
C NE SW

Total Depth. 5775'  
Comm. 4-16-55 Comp. 5-11-55  
Shot or Treated.  
Contractor. Musgrove Petro. Corp.  
Issued. 6-18-55

County Seward KANSAS



Elevation. 2801' RB

Production. Dry

CASING:

13 3/8" 578' cem w/525 sx  
8 5/8" 2719 1/2' cem w/225 sx

Figures indicate Bottom of Formations

sand	50
sand & clay	520
red bed	530
shale & red bed	580
red shale & lime strks.	820
sand & red bed	950
anhydrite	995
anhydrite & shale	1040
sand & shells	1160
red shale & shells	1664
shale & lime shells	1700
shale & shells	1752
lime	1783
shale	1820
lime & shale	2225
anhydrite & shale	2365
anhydrite & lime	2435
anhydrite	2575
anhydrite & lime shells	2612
lime	2755
lime & shale	2934
lime	3081
lime & shale	3449
lime	3540
lime & shale	3686
lime	3939
lime & shale	4050
lime	4312
lime & shale	4400
lime	4853
lime & shale	4945
lime	5560
lime & shale	5590
lime	5775 RTD
Total Depth	

Tops: Scout	
Towanda	2807
Ft. Riley	2867
Topeka	3952
Heebner	4284
Toronto	4302
Lansing	4401
Marmaton	5040
Cherokee	5224
Mississippi	5612