

31-32-31W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- PANHANDLE EASTERN PIPE LINE CO.
Farm- Sherer No. 1

SEC. 31 T. 32 R. 31W
C SE/4

Total Depth. 5850'
Comm. 1-16-59 Comp. 2-17-59
Shot or Treated.
Contractor. Lynn Drlg. Co.
Issued. 3-21-59

County Seward
KANSAS



CASING:
8 5/8" 2565' cem w/125 sks HA-5, 400 sks. common Elevation. 2773.70' GL

Production. Dry

Figures indicate Bottom of Formations.

sand	525
red bed	875
red bed & shells	1625
red bed, shells, shale	1736
Anhydrite & shale	2410
Anhydrite & dolomite	2556
lime & shale	3575
lime	4038
lime & shale	4623
lime	5220
lime & shale	5850
Total Depth	

TOPS:	
Upper Krider	2612
Winfield	2696
Council Grove	2910
Toronto	4273
Lansing	4379
Des Moines	5006
Oswego	5126
Cherokee	5169
Morrow Shale	5509
Morrow Sand	5580-88
Morrow Sand	5598-5607
Chester	5607
St. Genevieve	5781