

508 East Murdock
Wichita, Kansas

JAN 18 1969

DRILLER'S LOG

35-32-31 W

WELL NAME: GANO "A" No. 2; COMPANY OPERATING: Anadarko Production Company
ADDRESS of COMPANY: Box 351 Liberal, Kansas 67901
WELL LOCATION: C $\frac{1}{4}$ SW $\frac{1}{4}$ SW $\frac{1}{4}$,
600 ft. North of South line,
600 ft. East of West line: Sec. 35, Twp. 32S, Rge. 31W, Seward County, Kansas
DRILLING STARTED 11-9, 1968; DRILLING COMPLETED 11-29, 1968
WELL COMPLETED 12-10, 1968; WELL CONNECTED _____, 19____
ELEVATION: 2773.7 ft. Ground Level; CHARACTER OF WELL (Oil, Gas, or Dry Hole) Dual Oil

OR GAS SANDS OR ZONES - PERFORATIONS - ACIDIZING AND FRACTURING INFORMATION

Name	From	To	No. of Shots	Gallons Used	Kind Used
St. Louis	5913'	5916'	12	3,000	15% N.E.
Marmaton	5083'	5087'	16		

CASING RECORD

Size	Amount Set	Sacks of Cement	Amount Pulled
8 5/8"	1619'	800	None
5 1/2"	6019'	475	None
Str #1 2 1/16"	5898'		None
String #2 2 1/16"	5082'		None

FORMATION RECORD

Formation	Top	Bottom	Formation	Top	Bottom
Surface Sand & Shale	0'	234'	Lime	5580'	6020'
Sand & Shale	234'	1565'	Total Depth	6020'	
Shale & Anhydrite	1565'	1620'			
Anhydrite	1620'	1632'			
Sa & Shale-Redbed	1632'	2145'			
Sh. <u>Shale</u>	2145'	2690'			
Shale & Lime	2690'	3050'			
Lime <u>Lime</u>	3050'	3188'			
Lime & Shale	3188'	4064'			
Li.	4064'	4180'			
Lime & Shale	4180'	4616'			
Lime	4616'	5520'			
Lime & Shale	5520'	5580'			

RESULTS of INITIAL PRODUCTION TEST: St. Louis zone: In 6 hours, swabbed 31.72 B.O. G.O. 8% B.S.
Marmaton zone: In 8 hours, flowed 117.80 B.O. G.O. 3% B.S.