

OCT 18 1969

DRILLER'S LOG

WELL NAME: Gano "A" No. 3; COMPANY OPERATING: Anadarko Production Company
 ADDRESS of COMPANY: Box 351 Liberal, Kansas 67901
 WELL LOCATION: W/2 1/4 NE 1/4 SW 1/4,
1980 ft. North of South line,
1680 ft. East of West line: Sec. 35, Twp. 32S, Rge. 31W, Seward County, Kansas
 DRILLING STARTED 6-11, 1969; DRILLING COMPLETED 6-29, 1969
 WELL COMPLETED 7-17, 1969; WELL CONNECTED 7-23, 1969
 ELEVATION: 2767.4 ft. Ground Level; CHARACTER OF WELL (Oil, Gas, or Dry Hole) Oil


OIL OR GAS SANDS OR ZONES - PERFORATIONS - ACIDIZING AND FRACTURING INFORMATION					
Name	From	To	No. of Shots	Gallons Used	Kind Used
St. Louis	5965	5969	8	Set Baker Model "K" Cmt.	Ret. @ 5957'
				Squeezed perfs W/100 sx	Common.
St. Louis	5942	5947	10	Acidized 500	15% NE
				Set Baker Ret BP @ 5921'	
St. Louis	5890	5896	12	Acidized 2000	Mod 202
				Recovered BP	

CASING RECORD

Size	Amount Set	Sacks of Cement	Amount Pulled
8 5/8"	1610'	800	None
4 1/2"	6055'	340	None
2 3/8"	5898'	SN @ 5878'	

FORMATION RECORD

Formation	Top	Bottom	Formation	Top	Bottom
Sand & Gravel	0	1022'			
Sand, Redbed & Anhydrite	1022'	1611'			
Anhydrite	1611'	1622'			
Red bed, Shale, Anhy-	1622'	2548'			
drite	2548'	3684'			
Lime & Shale	3684'	5408'			
Lime	5408'	6056'			
Total Depth	6056'				



RESULTS of INITIAL PRODUCTION TEST: In 8 hrs. flowed 53.34 BF 9% Water