

State Geological Survey

WICHITA BRANCH
KANSAS DRILLERS LOG

15-175-20332

API No. 15 — 175 — 20,332
County Number

Operator
ANADARKO PRODUCTION COMPANY

Address
P. O. BOX 351, LIBERAL, KANSAS 67901

Well No. Lease Name
7 GANO "A"

Footage Location
663.5 feet from (N) (S) line 992 feet from (E) (W) line

Principal Contractor Geologist
Gabbert-Jones, Inc. Joe Blair


Spud Date Total Depth P.B.T.D.
10/12/77 3220'

Date Completed Oil Purchaser
11/9/77

S. 35 T. 32S R. 31 E W
Loc. 663.5 FSL & 992' FWL

County Seward

640 Acres
N



Locate well correctly

Elev.: Gr. 2768.8'

DF KB

CASING RECORD

Report of all strings set—surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8"	20#	522'	Common	500	3% CaCl
Production	7-7/8"	4-1/2"	10.5#	3219'	Lite Wate S. S. Pozmix	400 150	4% gel, 12-1/2# gil/sk, .05CFR-2

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2		3112-3142'
			2		3050-3099'

TUBING RECORD

Size	Setting depth	Packer set at			
2-1/16"	3082'				

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
A/500 gals 15% NE, sqd w/100 sxs Common	3112-3142'
A/2500 gals 15% NE + 45BS	3050-3099'

INITIAL PRODUCTION

Date of first production SI, WOPL Conn.	Producing method (flowing, pumping, gas lift, etc.) Flowing
RATE OF PRODUCTION PER 24 HOURS	Oil Gas Water Gas-oil ratio
	bbls. 750 MCF bbls. CFPB
Disposition of gas (vented, used on lease or sold)	Producing interval(s) 3050-3099'

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on an open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

operator

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:

ANADARKO PRODUCTION COMPANY

GAS

Well No.

Lease Name

7

GANO "A"

S 35 T 32 S R 31 W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Surface Clay-Sand	0'	522'		
Sand-Redbed	522'	726'		
Redbed-Sand-Shale	726'	1525'		
Redbed-Sand-Anhy	1525'	1966'		
Shale	1966'	1987'		
Sand-Shale	1987'	2345'		
Lime-Shale	2345'	3220'		
TOTAL DEPTH		3220'		
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.				

Date Received

Signature

Paul Campbell, Division Production Manager

Title

February 15, 1978

Date