

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

35-32-31W

Company- Ambassador Oil
Farm- Saunders

No. 1

SEC. 35

T. 32
CNW

R. 31W

Total Depth. 6078

Comm. 10-8-64

Comp. 10-23-64


Shot or Treated.

Contractor. Unit Drlg. # 2

Issued. 4-10-65

County Seward

KANSAS



CASING:

8" 608' 600 sx.

4" 5590' 250 sx.

Elevation. 2733' KB

Production. 121 BOPD

Figures Indicate Bottom of Formations.

lime, white-cream	3008
lime, white-cream	3034
lime, very fossiliferous	3106
lime, fair porosity	3168
lime, fair to good	3214'
lime, fair to good	3263
" " " "	3290
lime, white, slightly chalky	3334
" " " "	3772
lime, white, chalky	3834
" " " "	4210
lime, scattered good porosity	4260
lime, good fluorescence, no cut	4334
lime, no shows	4511
lime, good porosity	4625
lime, fair	4688
lime, fair porosity	4796
lime, cream tan-buff	4913
lime, show of free oil	5117
lime, fair cut & stain	5830
lime, show of free oil	6028

DST # 4 5091-5130/60" GTS 20", gauged 47 MCF, Rec. 1470' free oil, 310' heavy oil & gas cut mud. 450' O. & G. cut mud, FP 590-1077#, BHP 1603#/30".

DST # 5 5500-55/1 1/2 hrs. GTS-3" gauged 280 MCF, Red. 190' salty mud, 450' gas cut muddy salt wtr. w/oilsatin, FP 228-223#, BHP 1880-1802#/30".

DST #6 5775-5840/25", weak blow & died, Rec. 15' mud, FP 54-170#, BHP 54-296#/30".

DST #7 5904-68/1 1/2 hrs. rec 55' heavy mud, 680' saltwater w/sulphur odor, 120' HWCM w/specks of oil, FP 54-441#, BHP 1789-1634#/30".

A Schlumberger Dual Induction-Laterolog, with Sonic-Caliper & Gamma Ray logs were run on this well.

TOPS: LOG

Krider	2681
Winfield	2741
Frost Riley	2800
Wreford	2976
Council Grove	3015
Heebner	4278
Toronto	4306
Labsung	4414
Marmaton	3040
Cherokee	5218
Atoka Sand	5510
Morrow Sand	5548
Chester	5582
Chester Sand	5740
St Geneieve	5780
St. Louis	5854

DST #1 4310-40/60" GTS in 10", 50 MCF
REC. 140' MSW, 1530' SW, FP 249-304#
BHP 1320-1242#/30".

DST #2 4416-30/ 1 1/2 hrs. weak to fair blow,
Rec. 2' mud, slightly gas cut w/stks. oil,
90' muddy, oily salt wtr., FP 15-53#, BHP 1018#/30".

DST #3 5045-75/2 hrs. GTS 5", 10"-197 MCF,
90"-220 MCF, 180"-197 MCF, Red. 10' mud, 320'
salt wtr. cut mud, 400' heavy gas cut
muddy salt wtr. FP 102-141#, BHP 1653-1605#/30"