

NOV 8 1969

DRILLER'S LOG

WELL NAME: Traylor "A" No. 1; COMPANY OPERATING: Anadarko Production Company
 ADDRESS of COMPANY: Box 351 Liberal, Kansas 67901
 WELL LOCATION: C $\frac{1}{4}$ SW $\frac{1}{4}$ SE $\frac{1}{4}$,
660 ft. North of South line,
3300 ft. East of West line: Sec. 35, Twp. 32S, Rge. 31W, Seward County, Kansas
 DRILLING STARTED June 30, 1969; DRILLING COMPLETED July 18, 1969
 WELL COMPLETED July 25, 1969; WELL CONNECTED August 11, 1969
 ELEVATION: 2750.7 ft. Ground Level; CHARACTER OF WELL (Oil, Gas, or Dry Hole) Oil

OIL OR GAS SANDS OR ZONES - PERFORATIONS - ACIDIZING AND FRACTURING INFORMATION

Name	From	To	No. of Shots	Gallons Used	Kind Used
St. Louis	5901	5906	20	Acidized 1500	A 20.2

CASING RECORD

Size	Amount Set	Sacks of Cement	Amount Pulled
3 5/8"	1607'	800	None
4 1/2"	5999'	400	None
2 3/8"	5909'	SN @ 5892	

FORMATION RECORD

Formation	Top	Bottom	Formation	Top	Bottom
Sand, Red Bed & Shale	0'	61'			
Sand, Red Bed, Shale & Gypsum	61'	1578'			
Anhydrite	1578'	1608'			
Anhydrite & Shale	1608'	2472'			
Lime, Shale & Chalk	2472'	2914'			
Lime	2914'	4438'			
Lime & Shale	4438'	4666'			
Lime	4666'	4796'			
Lime & Shale	4796'	5790'			
Lime	5790'	6000'			
Total Depth	6000'				

RESULTS of INITIAL PRODUCTION TEST: In 11 hours swabbed 66.27 BF - 1.2% Water.