

4-42W MAP NO. 2-84 SEC. 26-32S-31W
 STATE Kans COUNTY Seward LOC. C SW SE

OPER. Ambassador Oil Corp - Okla City, Okla. PY/FR _____ LINE _____

WELL 1 FARM E.L. Richardson FT/FR _____ LINE _____

POOL Massoni Ext ELEV. _____ GR. 2791 DF 2794 KB _____

CONT. Wakefield Drlg. GEOL. Bill Broughton

F.R. 11-30-64 SPUD 12-9-64 COMP. 4-1-65

TD. 5986 FM. St L PBTD. _____

COMP. RECORD Mrw 5565-73 32 500A

4 Pt COF 16,800,000 Cfgpd & 6 B Dist/p million

8 5/8" @1572 w/850 sx. 4 1/2" @5754 w/300 sx.



Date Inc.

(KB Log)		<u>DST #1 (Atoka) 5515-50, Op 90", WB, R</u>
Hb	4302 -1508	<u>90' Sli GCM, ISIP 1653#/30", IFP 15#,</u>
Tor	4333 -1539	<u>FFP 44#, FSIP 588#/30"</u>
Lans	4444 -1650	<u>DST #2 (Chest sd) 5753-5810, Op 1 hr, WB,</u>
Marm	5066 -2272	<u>R 10' M, ISIP 131#/30", IFP 44#, FFP 54#,</u>
Atoka sd	5536 -2742	<u>FSIP 63#/30", RTD 5982, Sj Log, 4 1/2" @5754</u>
Mrw sd	5564 -2770	<u>w/300 sx., MICT 3-12-65, Pf 5565-73 (Mrw)</u>
Ches sd	5754 -2960	<u>Tbg w/pkr @5547, Ga 3,690,000 Cfgpd thru</u>
Ste G	5791 -2997	<u>24/64" choke, FTP 1125#, SITP 1600#/6 1/2</u>
St L	5864 -3070	<u>hrs, 500A (15%), Ga 4,070,000 Cfgpd &</u>

LTD 5986 -3192 6 B Dist/million/4 hrs thru 1/2" choke,
 RTD 5982 FTP 1200#, SITP 1560#/6 hrs, 4 Pt Cal OF:
16,800,000 Cfgpd & 6 B Dist/million,
SITP 1567#/67 1/2 hrs, Mrw perfs 5565-73 -
COMPLETED (3-29-65)

OKLAHOMA CITY ELECTRIC LOG TOPS

2794 KB

Winfield 2769 (+25)

Heebner 4313 (-1519)

Toronto 4334 (-1540)

Lansing 4443 (-1649)

Marmaton 5082 (-2288)

Morrow 5551 (-2757)

"S-1" Sand 5564 (-2770) 6/10; ϕ 16,800 MCF

Chester 5629 (-2835)

Sand 5791 (-2997)

St. Gen 5791 (-2997)

St. Louis 5864 (-3070)

TD 5986