

9-253W Map No. K-84

OPER ANADARKO PROD CO. - Liberal, Ks.



S-T-R 36-32S-31W

SPOT App C NW

CO SEWARD (Ks)

ELEV 2772 GR

WELL #1 EVANS "B"

FR Moran Brothers

FIELD Massoni (Multi Pay) O&G Ext

I.P. 1 Pt Cal OF 1,632,000 Cfgpd, Mrw 5573-75

(GR Log)

DST #1 (Atoka) 5510-24, Op 55", R 75' O&GCM & 135' SW,  
ISIP 1875#/40", FP's 62-108#, FSIP 1865#/40"

DST #2 (Mrw) 5558-5608, Op 8", GTS/3", Ga 1,860,000 Cfgpd/  
6", Op 40", Ga 3,020,000 Cfgpd/10" & stab, R 510' frothy  
O&GCSW, ISIP 1863#/40", FP's 726-578#, FSIP 1755#/40"

DST #3 (Str Pkr) (Lans) 4630-80, Op 45", R 475' SGCMSW,  
ISIP 1494#/40", FP's 145-249#, FSIP 1441#/40", RTD 5820,

Log

DST #4 (Str Pkr) (Mrw) 5556-5606, Op 4", GTS/2", Ga  
1,074,000 Cfgpd/3", Op 60", Ga 1,860,000 Cfgpd/5", Ga

2,061,000 Cfgpd/20", Ga 2,123,000 Cfgpd/30", Ga

2,172,000 Cfgpd/40", Ga 2,196,000 Cfgpd/45", Ga

2/220,000 Cfgpd/55" w/spray of drlg. flu, R 432' Flu, ISIP 1861#/35", FP's  
478-459#, FSIP 1808#/55", 4½" @5819w/150 sx., Pf 8/5573-75 (Mrw), Gas Ga

2,168,000 Cfgpd/1½ hrs, Ga 2,061,000 Cfgpd/8 hrs, 2 3/8" tbg @5561, SICP 1554#/  
49 hrs, SITP 1560#/49 hrs, SI - 24½ hr, 1 Pt Cal OF: 1,632,000 CFGPD - SITP

5/139½ hrs, SICP 1560#/139½ hrs, Mrw 5573-75 - COMPLETED on 9-20-65

CG	3008 - 236
Hb	4266 -1494
Tor	4306 -1534
Lan	4414 -1642
Mar	5042 -2270
Cher	5192 -2420
Atoka Not Picked	
Mrw	5524 -2752
Chest	5592 -2820
Ste G	5764 -2992
LTD	5817 -3045

Data, Inc

MISCEL DATA

GEOL Co. Geol

FTG

SUPPT

CSG 8" @1640 w/850 sx. 4" @5819 w/150 sx.

L-S 2781 DF

ELEV 2782 DF

2785 KB

SPUD DATE 8-18-65

DRLG COMP

FR by DATA 8-16-65

COMP by " 9-23-65

LIBERAL ELECTRIC LOG TOPS

2772 GL

Winfield 2732 (+40)  
Heebner 4292 (-1520)  
Toronto 4306 (-1534)  
Lansing 4412 (-1640)  
Marmaton 5042 (-2270)  
Morrow 5524 (-2752) 5/por.  
Sand 5570 (-2798) 7/12;  $\phi$  1,632 MCF  
Chester 5592 (-2820)  
Ste. Gen ? 5800 (-3028)  
TD 5817