


12-222W Map No. K-54
 OPER. ANADARKO PROD. CO. - Liberal, Ks.
 WELL #1 GANO "A"
 CO. Moran Brothers Drlg.
 FIELD Massoni (Multi Pay O&G) Field
 I.P. Ga 1,780,000 Cfgpd, Mar 5028-5133



S-T-R 35-32S-31W
 SPOT C NE SW
 CO SEWARD (Ks)
 ELEV 2764 GR

(GR Log)

Kri	2634	+	130
Winf	2698	+	66
U/FR	2758	+	6
L/FR	2828	-	64
FF	2876	-	112
Wre	2931	-	167
C Gr	2975	-	211
Hb	4245	-	1481
Tor	4272	-	1508
Lan	4382	-	1618
KC	4638	-	1874
Mar	5008	-	2244
LTD	5194	-	2430

DST #1 (Mar) 5015-90, Op 50", GTS/6", Ga 240,000 Cfgpd/5", Ga 416,000 Cfgpd/40", R 30' M, ISIP 1701#/40", FP's 105-140#, FSIP 1701#/40"
DST #2 (Mar) 5114-48, Op 10", GTS/2", Op 40", Ga 2,310,000 Cfgpd/5", Ga 3,120,000 Cfgpd/10", Ga 3,400,000 Cfgpd/20", Ga 3,400,000 Cfgpd/30" & stab, R 2 gal wtr & cond, ISIP 1701#/40", FP's 347-397#, FSIP 1701#/40"
 RTD 5190, Welex Log
WLT #1 (KC) 4868-70½, Op 1 hr, R 650 cc wtr (13% form wtr) ISIP NA, SP 50#, FSIP 50#/20" 4½" @5190 w/200 sx.
Pf 12/5130-33 (Mar), Ga 1,635,000 Cfgpd/1½ hrs w/ mist wtr, Pf 16/5028-32 (Mar), Ga 1,650,000 Cfgpd w/mist wtr/2 hrs, 2 3/8" tbg @5007 - WHSIP 1460#/163 hr, SIBHP 1697.8# 163 hr, 4 Pt OF: Ga 1,780,000 CFGPD, FTP 1216#, FCP 1240#, Mar 5028-5133 - COMPLETED on 12-9-65

Data Inc

*L-S 2773 EDF
2764 GR*

MISCEL DATA
 GEOL _____ ELEV 2775 DF SPUD DATE 11-9-65
 FTG _____ 2777 KB DRLG COMP _____
 SUPPT _____ FR by DATA 9-28-65
 CSG 8" @1617 w/850 sx. 4½" @5190 w/200 sx. COMP by " 12-16-65

LIBERAL ELECTRIC LOG TOPS

2764 GL

Winfield 2696 (+68)

Heebner 4258 ~~(-1494)~~ 4245 (-1481)

Toronto 4272 (-1508)

Lansing 4382 (-1618)

Marmaton 5008 (-2244) ϕ 1,780 MCF

TD 5194