

6-32-32W

KANSAS WELL LOG BUREAU--- KANSAS GEOLOGICAL SOCIETY
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY CITIES SERVICE OIL CO.

SEC. 6 T. 32 R. 32W

FARM Cotton

NO. 1

LOC. SE SE NW
100' N & 100' W
of center

TOTAL DEPTH 2800'

COMM. 9-26-50


COMP. 10-3-50

SHOT OR TREATED

CONTRACTOR Baco Drlg. Co.

ISSUED 6-2-51

COUNTY Seward



CASING

8 5/8" 520' cem w/250 sxs.
5 1/2" 2799' cem w/700 sxs.

ELEVATION 2859

PRODUCTION 6,850,000 gas

FIGURES INDICATE BOTTOM OF FORMATIONS

clay & sand	485
red bed	530
red bed & sand	1005
gyp	1088
red bed	1200
sand	1357
sand & red bed	1657
anhydrite & red bed	1902
shale & lime	2024
shale & anhydrite	2380
lime & anhydrite	2490
shale & anhydrite	2585
shale, anhydrite & lime	2736
shale & lime	2800
Total depth	

Tops:

Herington	2634
Upper Krider	2659
Lower Krider	2693
Winfield	2740

Perforated:

60 shots	2636-46
64 shots	2660-68
140 shots	2686-2714
80 shots	2740-50

SIP 417.9#