

WICHITA BRANCH

This form must be filed in triplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within five days after the completion of the well, regardless of how the well was completed. Circle one: Oil, gas, dry, SWD, OWWO, injection. Please type. Complete ALL sections. Applications must be filed for dual completion, commingling, salt water disposal and injection. Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.) KCC#-(316) 263-3238.

OPERATOR Petroleum Inc. API NO. 15-175-20556
ADDRESS P. O. Box 1255 COUNTY Seward
Liberal, KS 67901 FIELD Wildcat
**CONTACT PERSON Merle Evers LEASE Irwin
PHONE 316-624-1686

PURCHASER NA WELL NO. 2
ADDRESS _____ WELL LOCATION NE SW NW/4
_____ 1660 Ft. from North Line and
_____ 880 Ft. from West Line of
the SEC. 34 TWP. 32S RGE. 32W

DRILLING CONTRACTOR Zenith Drilling
ADDRESS 505 Fourth Financial Center
Wichita, Kansas 67202


PLUGGING CONTRACTOR Dowell
ADDRESS Ulysses, Kansas
TOTAL DEPTH 6110' PBTD _____

SPUD DATE 10/10/81 DATE COMPLETED 10/22/81

ELEV: GR 2810 DF 2818 KB 2820

DRILLED WITH (~~CABLE~~) (ROTARY) (~~WIR~~) TOOLS

Report of all strings set — surface, intermediate, production, etc. (New) / (~~REPAIR~~) casing.



WELL PLAT
(Quarter) or Full Section - Please indicate.

KCC _____
KGS ☒
MISC. _____

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs./ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	7 7/8	8 5/8	24#	1626	Liteweight Class "H"	700 200	3/4#floseal, 2%cc 3%cc

LINER RECORD			PERFORATION RECORD		
Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
TUBING RECORD					
Size	Setting depth	Packer set at			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

TEST DATE: _____

PRODUCTION

Date of first production	Producing method (Flowing, pumping, gas lift, etc.)				A.P.I. Gravity
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	CFPB
	bbbl	ACF	bbbl		
Disposition of gas (vented, used on lease or sold)			Producing interval(s)		

** The person who can be reached by phone regarding any questions concerning this information

A witnessed initial test by the Commission is required if the well produces more than 25 BOPD or is located in a Basic Order Pool.

NOV 12 1981

Name of lowest fresh water producing stratum Unknown Depth 550
Estimated height of cement behind pipe surface

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
DST #1 4270-4300 30"-60"-60"-120" IHP - 2035 FHP - 2003 IFP - 81-212 FFP - 245-326 ISI - 882 FSI - 898 REC. 120' muddy salt water slightly gas cut; 540' slightly gas cut salt water			Winfield Council Grove Heebner Toronto Lansing Marmaton Cherokee Morrow Chester St. Gen. St. Louis	2736 2952 4243 4282 4370 5008 5190 5513 5637 5834 5929
DST #2 4369-4383 30"-60"-60"-120" IHP - 2141 FHP - 2093 IFP - 32-48 FFP - 80-112 ISI - 1273 FSI - 1257 REC. 60' watery mud; 120' salt water				
DST #3 5928-5940 30"-60"-60"-120" IHP - 2867 FHP - 2835 IFP - 64-80 FFP - 96-129 ISI - 1803 FSI - 1819 REC. 150' oily drlg. mud; 30' watery oily mud; 60' salt water				
DST #4 5568-5640 Misrun				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

AFFIDAVIT

STATE OF Kansas, COUNTY OF Seward SS,

Merle Evers OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS OATH, DEPOSES AND SAYS:


THAT HE IS Dist. Superintendent FOR Petroleum Inc.
OPERATOR OF THE Irwin LEASE, AND IS DULY AUTHORIZED TO MAKE THIS
AFFIDAVIT FOR AND ON BEHALF OF SAID OPERATOR, THAT WELL NO. 2 ON SAID LEASE HAS
BEEN COMPLETED AS OF THE 24 DAY OF October 19 81, AND THAT ALL
INFORMATION ENTERED HEREIN WITH RESPECT TO SAID WELL IS TRUE AND CORRECT.

FURTHER AFFIANT SAITH NOT.

(S) Merle Evers

SUBSCRIBED AND SWORN TO BEFORE ME THIS 11th DAY OF November 1981

MY COMMISSION EXPIRES: _____



James R. Hatfield
NOTARY PUBLIC