


3 - 32 - 33 W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- STANOLIND OIL & GAS CO.
Farm- Hille Gas Unit No. 1

SEC. 3 T. 32 R. 33W
SW SW SW NE
2490 S of NL & 2490 W of
EL
County Seward
KANSAS

Total Depth. 2736 P.B. 2724
Comm. 8-2-54 Comp. 9-6-54
Shot or Treated.
Contractor.
Issued. 12-18-54



Elevation. 2895 D. F.

Production. 4,509,000 gas

Figures indicate Bottom of Formations.

sand, shale blue	570
red rock	630
shale	1000
shale, salt	1600
shale, shells	2343
shale, anhyd.	2455
lime, Anhyd.	2533
lime, shale	2593
shale, anhyd.	2660
lime	2736
Total Depth	

Tops:
Herington 2679
Krider 2714

Se Lumberger ran Gamma Ray & Micro log
Chemical process acidized.

Krider 2500 gal 15%
Herington 2500 gal 15%
All zones 7000 gal 7½%

McCullough perf. w/6 shots per ft. as
follows:
Herington 2679-83, 2685-90, 2698-2701