

6-32-33W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- PANHANDLE EASTERN PIPE LINE CO.  
Farm- Ellis No. 1

SEC. 6 T. 32 R. 33W  
C SW NE

Total Depth. 2670'  
Comm. 12-17-57 Comp. 12-24-57  
Shot or Treated.  
Contractor, Garvey Drlg.  
Issued. 10-10-59

County Seward  
KANSAS



Elevation. 2772' GL

Production. Gas Well

Figures indicate Bottom of Formations.

sand & shale	608
red rock & shale	840
sand & shale	940
red bed	1600
shells & shale	2050
shale	2145
lime & shale	2265
lime	2318
Anhydrite	2370
lime	2532
lime & shale	2597
lime	2670
Total Depth	

TOPS:

Herrington	2485
Krider	2513
Winfield	2591

Producing Formation:  
Krider 2513-2574  
Winfield 2591-2618

Perfs: 2601-06' w/4 sh/ft  
2593-2601; 2514-2570 w/2 sh/ft.

Treatment Record:  
A/500 gals. 15% 1-4-58  
A/6000 gals. 15% 1-5-58  
F/6000 gals. gelled acid, 9,000# sand  
& flushed w/5000 gals. 7½% 1-8-58


**WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY**  
 508 East Murdock, Wichita, Kansas

Company- **PANHANDLE EASTERN PIPELINE**  
 Farm- **Ellis** No. **1**

SEC. **6** T. **32** R. **33W**  
 C SW NE

Total Depth. **2670'**  
 Comm. **12-17-57** Comp. **1-8-58**  
 Shot or Treated.  
 Contractor.  
 Issued. **3-14-59**

County **Seward**  
**KANSAS**



Elevation. **2776'** RB

Production. **2,000,000** CFG

**CASING:**

8" **600'**  
 4" **2660'**

Figures indicate Bottom of Formations.

sand, shale	315
red bed, shale	840
sand, shale	940
red bed	1465
red bed	1600
shale, shells	2050
shale	2145
lime, shale	2265
lime	2318
Anhydrite	2370
lime	2532
lime, shale	2670
Total Depth	

**TOPS: SCOUT**

Herington	2485
Krider	2513
Winfield	2591

Ran Perforating Guns Atlas Log.