

Company - SPENCER CHEMICAL COMPANY
Farm - Mercer No. 1

SEC. 20 T. 32 R. 33W
CSL SE
1320' fr EL & 150' f SL

Total Depth. 2547
Comm. 12-15-49
Shot or Treated. Acid
Contractor. Baco Drilling
Issued. 6-3-50

Comp. 1-9-50

County. Seward
KANSAS



CASING:

10 3/4" O.D. 492' cem. w/400 sx.
7" O.D. 2442' cem. w/350 sx.
5 1/2" O.D. 122' liner.

Elevation. 2700 Ind

Production. 13,000,000 gas

Figures indicate Bottom of Formations.

surface clay & sand	50
clay brn & sand	323
sand, gyp & redbed	503
red bed	810
sand & red bed	1215
red bed, sand, & gyp	1496
shale blue, sand &	
red bed	1857
shale & anhyd.	1910
red bed, shale	2097
shale blue & anhyd.	2258
anhyd. & red bed	2340
anhyd.	2387
anhyd. & lime	RTD 2449
lime	2459
Herington lime	2477
lime & shale	2487
Krider lime	2525
shale	2537
Winfield lime & lime	
sdv	2547
Total Depth	

At T.D. - 2526' Acidized w/1000 gals.
15% acid. At T.D. - 2547' Acidized w/3000 gals.
15% acid. Re-acidized w/10,000 gals. 15% acid.

After cleaning up well- 72 hr 20 min.
open flow 13,000 MCF press. 447#.