

Operator

Burnett Corporation

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:
Oil Well

Well No.

1-26

Lease Name

Carlile

S 26 T 32 R 33 ^K/_W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
DST No. 1 4880-4908' (4900-4928' Elect. Log). Good Blow. GTS 5". Max ga 320 MCF 20". Op 30", SI 1 hr., Op 1 hr, Max ga 311 MCF 10". Op 1 hr. SI 2 hrs. Reg 741' gas cut oil & 30' SW. Gr. 40° @ 50° F. IHP 2313, IFP 165-298, ISIP 1592, FFP 215-348, FSIP 1592, FHP 2313.				
DST No. 2 4910-54' (4930-4974' Elect. Log). Op 1 hr, SI 1 hr, Op 1 hr, SI 1 hr. Rec 870'SW. IHP 2351, IFP 48-323, ISIP 1514, FFP 323-404, FSIP 1514, FHP 2351.				
DST No. 3 5540-5589' (5560-5611' Elect. Log). Op 1 hr, SI 1 hr, Op 1 hr, SI 1 hr. Rec 90' mud. IHP 2739, IFP 64-97, ISIP 97, FFP 97-97, FSIP 97, FHP 2739.				
<u>Electric Log Tops</u>				
Base Stone Corral Anhydrite Chase Group	2526	1607		
Heebner Shale	4140			
Toronto	4158			
LKc	4272			
Marmaton	4904			
Cherokee Shale	5100			
Morrow Shale	5446			
Chester	5598			
Ste. Genevieve	5778			
Log T. D.	5871			

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Signature

Clifford C. Vaughan

Vice President

Title

July 5, 1979

Date