


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 East Hurdock, Wichita, Kansas

Company - SPENCER CHEMICAL COMPANY
Farm - Lemert No. 2

SEC. 28 T. 32 R. 33W
CE 1/2 E 1/2 SE
1320' from SL, 380'
from EL

County. Seward
KANSAS



Total Depth. 2535
Comm. 2-17-50 Comp. 3-6-50
Shot or Treated. 16000 gals acid
Contractor. Baco Drilling Co.
Issued. 5-13-50

CASING:
10 3/4" 442' cem w/400 sx
7" 2526' cem w/350 sx
5 1/2" 131'

Elevation. 2683.2 and

Production. 12,908,000 gas

Figures Indicate Bottom of Formations.

surface clay, sand 375
red beds, gravel 417
red beds 655
red beds, gyp, sand 1158
red beds, sand, shale 1487
shale, red bed, anhy 1800
anhy., shale, shells 1907
shale, anhydrite 2071
anhydrite, red beds 2181
red beds, shale, line 2265
shale, anhydrite 2336
anhydrite 2356
Hollenberg Dolomite 2370
anhydrite, line, shale 2423
Herington Dolomite 2433
shale, line 2441
Herington Dolomite 2460
Rotary total depth 2450
shale, line 2480
Krider Dolomite 2519
shale, dolomite 2530
Winfield Dolomite 2535
Total Depth

Tops: Scout
Herington 2445
Krider 2480
Winfield 2530