

31-32-33W

KANSAS WELL LOG BUREAU---KANSAS GEOLOGICAL SOCIETY

508 EAST MURDOCK - WICHITA, KANSAS

COMPANY CABOT CARBON COMPANY

FARM Viola Corrigan et al No.1

SEC. 31 T. 32 R. 33W

LOC. NW NW SE

330' E & S of Center

TOTAL DEPTH 2665 2660 SLM

COMM. 10-13-50

COMP. 11-22-50


SHOT OR TREATED Acid 21,000 gals

CONTRACTOR Hills & Hills

ISSUED 3-24-51

COUNTY Seward

KANSAS



CASING

10 3/4" 521' cem w/250 SX

7" 2574' cem w/750 SX

5 1/2" liner 101'

2866 Ind.
2861.05

ELEVATION

PRODUCTION I.P.A. 22,736,000
gas

FIGURES INDICATE BOTTOM OF FORMATIONS

sand, gravel	0- 500
clay	505
red bed	529
red shale, (sandy)	1050
shale, shells	1660
shale, gyp	2130
lime, shale	2380
anhydrite	2455
lime broken	2500
lime, shale	2580
gas	2580-2590
lime	2658
shale	2660
lime	2665
Total Depth	S.L.M. 2660

*Scout
Herr
Upper Kri
Lower Kri
Winfield*

2570
2590
2610
2654

Scout Tops:
Herrington 2570
Upper Kri 2602?
Winfield 2650?

Show of gas 2580-2590
Inc. of gas 2610-2650
Inc. of gas 2660-2665

I.P.N. .600 M

Rock Pressure: 419.0