

DEC 19 1970

32-32-3340  
SE NE SW

DRILLER'S LOG

Company:	Cabot Corporation	Commenced:	10-6-70
Farm:	<u>Ruth Fischer No. 1-32</u>	Completed:	10-27-70
Location:	<u>1650' FSL &amp; 2310' FWL</u>	Contractor:	Leonard Hudson
	<u>Section 32-32S-33W</u>	Elevations:	2854' KB
	Seward County, Kansas		2852' DF
Casing:	8-5/8" @ 1640'/875 sacks		2842' GL
Perforations:	None	Total Depth:	6350' Rotary
			6357' Electric Log
		Production:	None - <u>Dry &amp; Abandoned</u>

*mm*

0 - 450'	Sand and Gravel
450 - 1030'	Red Bed and Gyp
1030 - 1600'	Red Bed, Sand, Gyp and Salt
1600 - 1640'	Anhydrite and Shale
1640 - 2160'	Red Bed and Anhydrite Shells
2160 - 2280'	Shale and Anhydrite
2280 - 2550'	Anhydrite and Shale
2550 - 2700'	Dolomite and Shale
2700 - 2870'	Lime and Shale
2870 - 3070'	Broken Lime and Shale
3070 - 3520'	Lime and Shale
3520 - 3750'	Lime
3750 - 4080'	Shale and Lime
4080 - 4250'	Lime and Shale
4250 - 4310'	Shale and Lime
4310 - 4910'	Lime and Shale
4910 - 5000'	Shale and Lime
5000 - 5170'	Lime and Shale
5170 - 5400'	Shale and Lime
5400 - 5560'	Shale and Lime Streaks
5560 - 5660'	Shale
5660 - 5770'	Shale, Sandy Lime and Sand
5770 - 5900'	Lime and Shale
5900 - 6030'	Limy Shale
6030 - 6110'	Lime and Sand
6110 - 6180'	Sandy Lime
6180 - 6350'	Lime and Chert
6350'	Driller's Total Depth

Formation Tops:

Winfield	2660'
Toronto	4189'
Lansing	4307'
Marmaton	4982'
Cherokee	5181'
Morrow	5560'
Lower Morrow Sand	5754'
Mississippi-Chester	5772'
Ste. Genevieve	6106'
St. Louis	6180'