

8-32-34W


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 E. Murdock, Wichita, Kansas

Company - CITIES SERVICE OIL CO.
Farm - Sloan No. 1

SEC. 8 T. 32 R. 34W
NW NW SE
200' S & 150' E. of Cen.

Total Depth. 2730
Comm. 7-7-49 Comp. 7-14-49
Shot or Treated. 23,000 gals. 15%
Contractor. Lohmann-Johnson Drlg.
issued. 2-18-50

County. Seward
KANSAS



CASING:

8 5/8" 520' cem. w/300 sx.
5 1/2" 2729' cem. w/700 sx.

Elevation. 2919.2nd.

Production. 12,100,000 gas
20 min. O.F.

Figures Indicate Bottom of Formations.

clay & sand	110
sand & shells	340
shale, sand & shells	495
red bed	800
shale & shells	1127
red bed & shale	1240
shale & sand	1595
shale & shells	1770
salt & shale	1870
shale & red ed	1930
shale & lime	2145
shale & shells	2240
lime & shale	2415
lime	2730
Total Depth	

Tops:
Herington 2582
Upper Krider 2616
Lower " 2641
Winfield 2686

Run Halliburton electric log.

Perforating record
140 shots 2686-2714
160 " 2642-74
25 " 2617-24
50 " 2580-90

Acidizing Record
7-21-49 3000 gals. 15% acid 2580-2674
" 2000 " 15% " 2686-2714
7-22-49 1500 " 15% " 2580-2624
" 8500 " 15% " 2580-2674
" 5000 " 15% " 2686-2714
7-24-49 9000 " 5% " to all zones.