

9-32-34W

KANSAS WELL LOG BUREAU --- KANSAS GEOLOGICAL SOCIETY
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY CITIES SERVICE OIL CO.


SEC. 9 T. 32 R. 34W

FARM Downing NO. 2

LOC. NE NE SW SW
1250' N. & 1250' E. of SWc

TOTAL DEPTH 2740 Corr.
COMM. 12-27-49 COMP. 1-4-50
SHOT OR TREATED
CONTRACTOR Corbett & Barbour Drlg. Co.
ISSUED 6-9-51

COUNTY Seward



CASING

8 5/8" 640' cem. w/325 sx
5 1/2" 2739' cem. w/700 sx

ELEVATION 2929

PRODUCTION 16,300,000 gas

FIGURES INDICATE BOTTOM OF FORMATIONS

clay	40
clay & sand	375
shale & shells	490
shale	540
red bed	641
red bed, shale & shells	1140
shale & shells	1220
sand & shale	1380
shale & shells	1680
shale	1700
anhydrite	1760
shale & shells	1865
shale & anhydrite	2025
shale & shells	2190
shale & anhydrite	2290
shale & shells	2350
shale, shells, & anhy.	2420
shale & anhydrite	2670
shale & lime	2745
2745 R.T.D. = 2740 Corr. to ground	
Total Depth	

Tops :	
Herington	2596
Upper Krider	2632
Lower Krider	2656
Winfield	2704

Perf:
30 shots 2598-2604
20 " 2634-38
160- " 2858-90
110 " 2704-26

S.I.P. 378.2