

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg. Wichita, Kansas


10 - 32 - 34 W

Company - CITIES SERVICE OIL CO.
Farm - Hickman No. 1

SEC. 10 T. 32 R. 34W
NW NW SE
100' S, 100' E of center.

Total Depth. 2800' 2795' corr. to ground
Comm. 5-27-48 Comp. 6-3-48
Shot or Treated. 10,500 acid
Contractor. Corbett-Barbour Drlg. Co.
Issued. 12-25-48

County. Seward
KANSAS



CASING:
8 5/8" 600' cem w/300 sx.
5 1/2" 2799' cem w/550 sx.
5 1/2" 2791' corr. to ground.

Elevation. 2913.2nd.

Production. 7,730,000 gas

Figures Indicate Bottom of Formations.

sand, shells 90
shale 395
sand, shells 540
redbed 1015
anhyd., shale 1135
sand, shells 1425
shale, shells 1560
salt 1695
shale 2000
shale, shells 2275
shale, lime 2535
lime 2800
total depth
T.D. 2795' corr. to
ground.

Ran Schlumberger
electric log.

Tops:

Herington 2630
Upper Krider 2664
Lower Krider 2687
Winfield 2734
Upper Ft. Riley 2794

Perf. 130 shots 2734-60.
6-22-48, 1500 gals. 15%
acid 2734-60
6-23-48, 5000 gals. 15%
acid 2734-60
1,830,000 gas
Perf. 160 shots 2688-2720
Perf. 50 shots 2630-40

6-25-48, 500 gals 15%
acid 2630-40.
" " " 1500 gals 15%
acid 2688-2720
6-28-48, 600 glas 15%
acid 2630-2720
" " " 4200 gals 5%
acid 2630-2720