

15 - 32 - 34W

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bldg. Wichita, Kansas

Company CITIES SERVICE OIL COMPANY
Farm Kapp "B" No. 1

SEC. 15 T. 32 R. 34W
NE NE SW
100' S & 100' W of Center

Total Depth. 2755'

Comm. 7-16-47


Comp. 8-2-47

Shot or Treated. Acidized

Contractor. Corbett-Barbour Drilling Company

issued. 3-13-48

County. Seward
KANSAS



Elevation. 2933 act & rh

CASING:

8-5/8" 720' Cem. w/325 sx

5-1/2" 2754' Cem. w/900 sx

Production. 20 Min. Open Flow
20,800,000 Gas

Figures indicate Bottom of Formations.

sand	0-450
shale & red bed	550
red bed	1015
anhydrite	1045
red bed & shale	1455
shale & red bed	1650
lime	1770
shale & red bed	2070
lime & shale	2135
shale & red bed	2267
shale & lime	2407
lime brkn	2482
lime & shale	2547
lime	2640
shale & lime	2675
lime	2755
Total Depth	

Schlumberger.

Tops:

Herington	2592
Upper Krider	2627
Lower Krider	2650
Winfield	2696
Fort Riley	2748

Top of cement 2731 SLM

Perforating Record:

136 shots 2699-2726, show gas
164 shots 2652-2683, show gas
85 shots 2628-2645, no inc.
60 shots 2592-2604, no inc.

Acidizing Record:

8-27-47 4000 gals. 15% 2592-2683
" 2000 gals. 15% 2699-2726

8-29-47 11000 gals. 15% 2592-2683
" 5000 gals. 15% 2699-2726
9-11-47 12000 gals. 5% to all zones.

Shut-in pressure 406.4#