

WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

19-32-34W


Company - CITIES SERVICE OIL CO.
Farm - Marteney "B" No. 1

SEC. 19 T. 32 R. 34W
NW NW SE
100' S & 100' E of Center

Total Depth. 2800'
Comm. 5-7-48 Comp. 5-15-48
Shot or Treated. Acid. 11/22,000 gals.
Contractor. Corbett-Barbour Drilg. Co.
Issued. 1-22-49

County. Seward

KANSAS



CASING:
8-5/8" 340' Cem. w/325 Sx.
5-1/2" 2729' Cem. w/900 Sx.

Elevation. 2942' sub.
2966' set v. h.
Production. 14,000,000 gas

Figures Indicate Bottom of Formations.

soil & sand	40
sand & shells	530
red beds	650
red beds & shale	1080
shale	1720
lime & shale	2630
lime	2800
Total Depth	

Schlumberger elec. log

Tops:

Herington	2608
Upper Krider	2638
Lower Krider	2668
Winfield	2714
Upper Ft. Riley	2778

Perf. 90 shots 2722-2740

5-21-48 1,000 gals. 15% 2722-2740
5-22-48 3,500 gals. 15% 2722-2740

2,150 MCF gas 2722-2740

Perf. 160 shots 2670-2702
" 50 " 2640-2650
" 60 " 2608-2620

5-26-48 1,000 gals. 15% acid 2608-2650
" 1,500 gals. 15% acid 2670-2702
5-27-48 5,500 gals. 15% acid 2608-2650
" 6,500 gals. 15% acid 2670-2702
5-29-48 9,000 gals. 5% acid to all zones