

24 - 32 - 34 W


WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - CITIES SERVICE OIL CO.
Farm - Donley No. 1.

SEC. 24 T. 32 R. 34 W
SEc NW
100' N 100' W Center

Total Depth. 2728'
Comm. 7-1-47 Comp. 7-11-47
Shot or Treated.
Contractor. Corbett-Barbour Drlg. Co.
Issued. 12-20-47

County. Seward
KANSAS



CASING:

8 5/8" 720' Cem.
5 1/2" 2727' Cem.

Elevation. 2923 feet

Production. 13,600,000 G.
20 Min. O.F. - S.I.F. 401.5#

Figures Indicate Bottom of Formations.

sand	0-260
clay & sand brks	445
red bed	1025
anhydrite	1090
red bed & shale	1530
shale & lime	1380
red bed & shale	1830
lime & shale	2145
shale & red bed	2239
lime & shale	2330
lime	2450
lime & shale	2548
lime	2605
lime & shale	2705
lime	2728
Total Depth.	

Berlington	2574
Upper Krider	2606
Lower Krider	2630
Winfield	2684

Drld cement to 2716 SIM

Perf. 40 shots 2574-62
20 shots 2610-14
190 shots 2632-70
150 shots 2684-2714

8-16-47 Az. 3300 gals. 15%
acid 2574-2670
8-16-47 Az. 2500 gals. 15%
acid 2684-2714
8-18-47 Az. 5500 gals. 15%

acid 2634-2714
8-18-47 Az. 8500 gals. 15%
acid 2574-2670
8-20-47 Az. 12000 gals. 5%
acid to all zones