

28-32-34W

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
508 E. Murdock, Wichita, Kansas


Company - CITIES SERVICE OIL CO,
Farm - Hitch "B" No. 1

SEC. 28 T. 32 R. 34W
NE NE SW
100' S & 100' W of Cen.

Total Depth. 2713
Comm. 12-8-48 Comp. 12-17-48
Shot or Treated. 24,500 gals.
Contractor. Midwestern Drilg. Co.
Issued. 2-18-50

County. Seward

KANSAS



Elevation. 2913 Ind.

Production. 17,000,000 gas
O. F. 20 min.

Figures Indicate Bottom of Formations.

surface soil	45
sand & clay	535
red bed	980
gypsum	1110
salt	1135
red bed & shale	1464
red bed	1664
red bed & shale	2145
lime	2165
shale & lime	2395
shale & anhyd.	2451
lime & shale	2496
lime	2634
lime & shale	2691
lime	2713
Total Depth	

Taps;	
Herington	2566
Upper Krider	2596
Lower "	2626
Winfield	2670

Perforating Record
70 shots 2568-2582
60 shots 2600-2612
150 shots 2628-2658
120 shots 2676-2700

Acidizing Record
12-21-48 1000 gals. 15% acid 2568-2612
" 1500 " " " 2628-2658
" 1000 " " " 2676-2700
12-23-48 13000 " " " 2568-2658
" 5000 " 5% acid to all zones.