

29-32-34W

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg. Wichita, Kansas

Company. CITIES SERVICE OIL COMPANY
Farm Hitch "B" No. 1

SEC. 29 T. 32 R. 34W
NE NE SW
100' S & 100' W of Center

Total Depth. 2775'
Commi. 10-13-47 Comp. 10-23-47
Shot or Treated. Acidized
Contractor. Lohmann-Johnson Drilling Co.
Issued. 3-13-48

County. Seward
KANSAS



Elevation. 2929 *end*

Production. 20 min. Open Flow
13,200,000 Gas

Figures Indicate Bottom of Formations.

sand & shale	0-500
red bed	642
red bed, sand & shale	900
sand & shale	1650
lime & shale	1881
shale	1990
lime & shale	2260
lime	2393
shale & lime	2538
lime	2580
lime & shale	2703
lime	2730
lime & shale	2775
Total Depth	

Tops:

Herington	2586
Upper Krider	2616
Lower Krider	2645
Winfield	2690
Upper Fort Riley	2738

Top of cement 2740 SLM.

Perforating Record:

130 shots 2694-2720
160 shots 2648-2680
80 shots 2616-2630
80 shots 2586-2602

Acidizing Record:

12-4-47 2000 gals. 15% 2694-2720
12-5-47 5000 gals. 15% 2694-2720
12-7-47 2500 gals. 15% 2586-2630
" 2500 gals. 15% 2648-2680
12-8-47 8000 gals. 15% 2586-2680
12-10-47 9000 gals. 5% to all zones.

Shut-In Pressure: 426.5#