

REC'D.	MAY 23 1927
INDEX	
MAPS	
GRAPH.	<i>CMW</i>
TYPED	
CC-S.F.	
FILE	

Seward County, Kansas.  
 VICKERS et al - HITCH LAND & CATTLE CO #1  
~~Hitch Land & Cattle Co., #1 Vickers~~  
 Loc: NE SW NE 33-32-34  
 Elev: 2881' -- Altimeter.

0	20	red shale	2430	2435	hard white lime
20	45	red sand	2435	2438	soft blue shale
45	140	gray sand	2438	2470	hard white lime
140	165	yellow sand	2470	2495	broken white lime
165	218	gray sand	2495	2608	blue shale
218	223	red shale	2608	2642	gray sandy lime
223	250	gray sand			I M gas at 2640'
250	282	light shale	2642	2715	dark sand (HPW)
282	335	blue shale	2715	2730	brown shale (at
335	355	brown shale	2730	2758	hard white lime (2708'
355	415	blue shale	2758	2774	soft gray sand (2772'
415	447	light shale	2774	2825	white sandy lime
447	757	red shale. HPW 757-67	2825	2866	hard white lime
757	929	red rock	2866	2873	brown shale
929	935	light sand	2873	2895	broken hard white lime
935	960	red shale	2895	2920	sandy white lime
960	972	white lime, hard	2920	2949	hard white lime
972	977	red shale	2949	2970	gray sandy lime
977	985	hard white lime	2970	2990	broken white lime
985	990	red shale	2990	3045	hard white lime
990	995	hard white lime	3045	3065	brown shale
995	1010	red shale	3065	3087	hard white lime
1010	1042	hard white lime	3087	3140	hard gray lime
1042	1048	light gray soft sand			
1048	1075	sandy brown shale			
1075	1080	red sand			
1080	1095	brown sandy shale			
1095	1140	red shale			
1140	1306	red sand			
1306	1635	red shale			
1635	1640	blue shale			
1640	1675	red shale			
1675	1695	hard white lime			
1695	1766	red shale			
1766	1770	brown shale			
1770	1870	red shale			
1870	1875	hard sandy light lime			
1875	1931	red shale			
1931	1938	hard white lime			
1938	2155	red shale			
2155	2210	blue shale			
2210	2230	blue hard lime			
2230	2265	blue shale and shells			
2265	2298	white lime			
2298	2319	blue shale			
2319	2325	hard white lime			
2325	2363	white lime shells			
2363	2395	hard white lime			
2395	2430	blue shale and shells			

Casing Record

356'	of	20"
799'	"	15 1/2"
1211'	"	12 1/2"
1925'	"	10"
2769'	"	8 3/4"

(Incomplete)