

4-219W

MAP NO. _____

SEC. 34-32S-29W

STATE Kans

COUNTY Meade

LOC C S/2 SW

OPER. C. Funk, L. Banks & W.R. Atkinson, Wichita, Ks. FT/FR _____ LINE _____

WELL #1 FARM Ediger (OWWO) FT/FR _____ LINE _____

TOL Borchers, NW (Extension) ELEV. 2672 GR. 2682 DF 2683 KB _____

CO. INT. _____ GEOL. _____

CO. INT.

F.R. 1/22/63 SPUD _____ COMP. 4/16/63


TD. 5803 FM. Miss-Chest PBT. 5700 (Est)

COMP. RECORD

Morr 5685-89 16 500 A & Frac

4 Pt COF; 5900 Mcfgpd + 1 B Dist/PH

9 5/8" @ 1458' w/950 sx. 5 1/2" @ 5798' w/240 sx.



Data Inc.

| (KB) Log | Elev. | 2683 KB |
|-------------------------|-----------------|---------|
| Herr 2710 - 27 | Lans 4574 | -1891 |
| Winf 2782 - 99 | Marm 5204 | -2521 |
| U/FR 2850 - 167 | Cher 5381 | -2698 |
| L/FR 2880 - 197 | Atoka 5493 | -2810 |
| FF 2920 - 237 | Morr sh 5677 | -2994 |
| Wref 2960 - 277 | Morr sd 5684 | -3001 |
| C.G. 3018 - 335 | Miss-Chest 5702 | -3019 |
| Limestone 3943-67 -1260 | LTD 3803 | -3120 |
| Hb 4423 -1740 | RTD 5803 | -3120 |

(OWWO) OLD INFO: (Was Raymond Oil #1 Ediger)

DST #1 (Morr) 5662-5703', Op 2 hrs & 15", Est Gas Ga 900 Mcfgpd,

R 80' Gas & Slightly Distillate Cut Mud, FBHP 1860#/30",

LTD 5803, 5 1/2" @ 5798' w/240 sx., & DV Tool @ 3396' w/230 sx.

Perf Morr 16/5685-89', 500 A & Frac (10,480 Gal Acid Gell +

9300# Sd), Rec Id, Ga 1700 Mcfgpd/2 hrs, Perf Marm 28/5263-70,

1000 A, \$ 25 BSWPH, Set Plug above Morr Perfs & Sqz Marm Perf

(Morr Perfs 5685-89 - Not Sqz), Sqz Marm Perfs w/100 sx., Perf

Lans 8/4614-16, Block Sqz w/100 sx., Perf Lans 20/4582-87, 1000 A,

\$ 15 BSWPH, Sqz 4582-87 w/100 sx., (Limestone Section - This

Zone perforated from Sj Log), Perf (Lm Stone) 3948-56', 1000 A,

No Fluid or Gas, Completed as D & A (12/24/62) (Pipe not pulled)

Sold to New Operator.

NEW INFO: (1/21/63) (To CO and Retest the Morrow) MICT, CO & Sqz

3948-56 (Top) w/Cem, CO Est 5700, (Morr Perfs 5685-89 are open)

4 pt Cal OF 5900 Mcfgpd + 1 B Dist PH, SIBHP 1565#. (PEPL buys

Gas)

COMPLETED (4/9/63)