

12-22-35W



KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY AIDMAN BROS. CORP
AIDMAN
FARM Larrabee NO. 3

SEC. 13 T. 32 R. 35W
LOC. C SE SW

COUNTY Stevens

KANSAS



TOTAL DEPTH 6190'
COMM. 6-9-68 COMP. 7-25-68
SHOT OR TREATED
CONTRACTOR Rine Drilling
ISSUED 11-2-68

CASING

20 10
15 8 5/8" 760' cem w/ 500 sx
12 6
13 5
4 1/2" 6189' cem w/ 225 sx

ELEVATION 2974' GL

PRODUCTION PMP 110 BOPD PLUS 15
% W, Gr 44/ Chest 6093-6117

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand & Red Bed 0' - 760'
Red Bed 760' - 1295'
Red 1 & Sand 1295' - 2106'
Red Bed & Anhydrite 2106' - 2380'
Shale & Lime 2380' - 3367'
Lime 3367' - 3795'
Limo & Shale 3795' - 3990'
Lime 3990' - 5645'
Shale & Lime 5645' - 6175'
Lime 6175' - 6190'

Totco - 1/4° @ 250'; 1/2° @ 500'; 1/2° @ 760'
Run 19 jts. 8 5/8 24# & 23# 760' & set @ 760' cem. w/350 sx. Haliburton lite wt. w/2% cc & 150 sx. common w/3% cc.

T.D.-Run 190 jts. 4 1/2" lonestar 10.5 & 9.5 csg. set @ 6189' cem w/225 sx. poz w/18% salt 12.5# coalite per sx. w/7% fluid loss additive.

STATE OF KANSAS)
COUNTY OF SEDGWICK)

SS

TOPS: SMP
Winfield 2723
Council Grove 2958
W-Wabaunsee 3332
Heebner 4193
Marmaton 4974
Morrow 5598
Upper Morrow sand 5652
Chester 5884
Lower Chester 6088
Lower Chester sand 6125
TD 6190

, R. M. Green, do hereby
o. 3-A, located SE of S

true and accurate log of the Larrabee Well
is County, Kansas.

