

SIDE ONE

STATE CORPORATION COMMISSION OF KANSAS
OIL & GAS CONSERVATION DIVISION
WELL COMPLETION OR RECOMPLETION FORM
ACO-1 WELL HISTORY
DESCRIPTION OF WELL AND LEASE

Operator: License # 5208
Mobil Oil Corporation
Name
Address
City/State/Zip Denver, CO 80217

Purchaser Permian

Operator Contact Person J. E. Dawson
Phone (303) 298-2696

Contractor: License # 9137
Unit Drilling & Exploration
Name
Phone (303) 298-3689

Wellsite Geologist T. N. Tvrdik
Phone (303) 298-3689

Designate Type of Completion

☒ New Well ☐ Re-Entry ☐ Workover
☒ Oil ☐ SWD ☐ Temp Abd
☐ Gas ☐ Inj ☐ Delayed Comp.
☐ Dry ☐ Other (Core, Water Supply etc.)

If ONWO: old well info as follows:

Operator
Well Name
Comp. Date Old Total Depth.....

WELL HISTORY

Drilling Method:

☒ Mud Rotary ☐ Air Rotary ☐ Cable

..8/6/86.... ..8/13/86.... ..8/27/86....
Spud Date Date Reached TD Completion Date

...6350..... ...6296.....
Total Depth PBTD

Amount of Surface Pipe Set and Cemented at.....feet
Multiple Stage Cementing Collar Used? ☒ Yes ☐ No
If yes, show depth set....3238.....feet
If alternate 2 completion, cement circulated
from.....feet depth to.....w/.....SX cmt
Cement Company Name
Invoice #

API NO. 15-189-20,924

County.....Stevens

C N/2 NE Sec. 15 Twp. 32S Rge. 35 East
..... XX West

4620 Ft North from Southeast Corner of Section
1320 Ft West from Southeast Corner of Section
(Note: Locate well in section plat below)


Lease Name.....Glenn McCulley.....Well #.....1.....

Field Name.....Unnamed

Producing Formation.....Chester

Elevation: Ground.....2971.....KB.....2987

Section Plat



WATER SUPPLY INFORMATION

Disposition of Produced Water: ☐ Disposal
Docket # ☐ Repressuring

Questions on this portion of the ACO-1 call:

Water Resources Board (913) 296-3717

Source of Water:

Division of Water Resources Permit #.....T86-285.....

XX Groundwater.....610.....Ft North from Southeast Corner
(Well)810.....Ft West from Southeast Corner of
Sec 10 Twp32S Rge 35 East XX West

Surface Water.....Ft North from Southeast Corner
(Stream, pond etc).....Ft West from Southeast Corner
Sec Twp Rge East West

Other (explain).....

(purchased from city, R.W.D. #.....)

METHOD OF COMPLETION

Production Interval

Disposition of gas: ☐ Vented
☐ Sold
☒ Used on Lease

☐ Open Hole ☒ Perforation
☐ Other (Specify)

☐ Dually Completed
☐ Conmingled

...6108-18.....

.....

*190 sxs 50/50 POZ + 2% gel

SIDE TWO

Operator Name Mobil Oil Corporation Lease Name Glenn McCulley Well # 1

Sec. 15 Twp. 32S Rge. 35 ☐ East ☒ West County Stevens

WELL LOG

	Oil	Gas	Water	Gas-Oil Ratio	Gravity
Estimated Production Per 24 Hours	134.88 Bbls	MCF	38 Bbls	CFPB	

Drill Stem Tests Taken ☐ Yes ☒ No
 Samples Sent to Geological Survey ☐ Yes ☒ No
 Cores Taken ☐ Yes ☒ No

Formation Description
☒ Log ☐ Sample

Frac Data Report:

500 gals 7½% FE acid
 1,000 gals Diesel Pre-Pad
 9,000 gals 60 Q Foam pad
 4,000 gals 60 Q Foam w/1 ppg 20/40
 4,000 gals 60 Q Foam w/2 ppg 20/40
 5,000 gals 60 Q Foam w/3 ppg 20/40
 5,000 gals 60 Q Foam w/4 ppg 20/40
 1,500 gals 60 Q Foam Flush

Name	Top	Bottom
Chase	2635	
Council Grove	2952	
Admire	3219	
Wabaunsee	3345	
Shawnee	3770	
Heebner	4157	
Lansing	4270	
Kansas City	4581	
Marmaton	4975	
Cherokee	5178	
Morrow	5602	
Chester "B"	5943	
Chester "A"	6030	
St. Genevieve	6128	
St. Louis	6257	
T.D.	6350	

CASING RECORD ☒ New ☐ Used

Report all strings set-conductor, surface, intermediate, production, etc.

Purpose of String	Size Hole Drilled	Size Casing Set (in O.D.)	Weight Lbs/Ft.	Setting Depth	Type of Cement	#Sacks Used	Type and Percent Additives
Surface	12½"	8 5/8"	24#	1808'	A-Lite	600	8% gel + 3% CaCl2
Production	7 7/8"	5½"	14#	6350'	A	90	2% CaCl2
					H	380	2% gel
					* 65/35/6	H 110	2% CaCl2

PERFORATION RECORD

Shots Per Foot	Specify Footage of Each Interval Perforated
4	6108-18

Acid, Fracture, Shot, Cement Squeeze Record

(Amount and Kind of Material Used)	Depth
(See Above)	

TUBING RECORD Size 2 7/8" Set At 6100 Packer at Liner Run ☐ Yes ☒ No

Date of First Production 9/4/86 Producing Method ☐ Flowing ☒ Pumping ☐ Gas Lift ☐ Other (explain).....