

90256

7225 W 83 ✓
 MAP NO. SEC. 24 TWP. 32S RGE. 35W
 STATE Kans COUNTY Stevens LOC. C SE SE
 OPERATOR J. M. Huber Corp. FT. FROM LINE
 WELL NO. 1 FARM NAME Boles FT. FROM LINE
 OL WC-5 miles SE of Clutter, * ELEV. 2974 GR 2981 DF 2984 KB
 FR. 6/5/62 SPUD. 6/21/62 COMP. 7/24/62

CONT. D & M Drlg. Co. /GEOL.

NAME PRODUCING INTERVAL COMPLETION RECORD FROM - TO PERF. W/HOLES TREATMENT RECORD

a					
b					
c					
d					

a I. P. OIL/DIST. WTR. GAS M.C.F.P.D. CHK. HRS.
 b " " " " " "
 c " " " " " "
 d

D & A

D & A ()

SIP# FI TP # FI CP# SIBHP
 GOR. GR. PSTD TD 6230
 SIZE DEPTH CASING - CEMENT RECORD SIZE DEPTH W/SAX.
 8 5/8" @ 2675 840

OPERATOR J.M. Huber Corp WELL NO. 1 Boles ELEV. 2984 KB

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
*So(Miss Oil) Pool)			KB Tops & Datums		
Wref	2925	+ 59	Hb	4182	-1198
CG	2960	+ 24	Tor	4206	-1222
Tor	4205		Lans	4304	-1320
Lans	4308		Marm	4992	-2008
Marm	5002		Chero	5190	-2206
			Morr Sh	5622	-2638
RTD(St Gen)	6230	-3246	Morr Sd zn	5840	-2856
			Chest	5887	-2903
			L/Chest Sd	6120-45	-3136
			St. Gen	6156	-3172

DST #1 (Lans) 4558-90, Op 2 hrs., R 11' mud, no sho & 437' my SW, IBHP 1325#/30", IFP 56#, FFP 242#, FBHP 1325#/30".

DST #2 (Marm) 4996-5016, Op 60", R 90' M & 450' SW, IBHP 1477#/30", IFP 43#, FFP 196#, FBHP 1430#/30".

DST #3 (Morr) 5825-63, Op 30", R 13' mud, no sho, all press 0#/30".

RTD 6230. S-j Log. D & A

COMPLETED

CORRECTION (6/12/62) Spot Was C SW SE Is C SE SE

LIBERAL ELECTRIC LOG TOPS

2984 KB

Winfield 2724 (+260)

Toronto 4205 (-1221)

Lansing 4303 (-1320)

Marmaton 5076 (-2092) tst 90' M + 450' XW

Morrow 5620 (-2636)

~~Marmaton~~ ~~Es~~ Morrow Ls 5841 (-2857) 4/9 ; 15' mud

Sand 5886 (-2902)

Chester 5898 (-2914)

Sand 6033 (-3049) 3/12

Sand 6120 (-3136) 12/26

Ste. Gen 6150 (-3166)

TD 6230 D & A.