


20012

83



Discovery
CSO contrib



1-142W Map No. _____
 OPER AIKMAN BROS. CORP.
 AMARILLO, TEXAS
 #1-A LARRABEE (TWIN)
 RINE DRLG. CO.
 4 1/2 MI SE/CUTTER SO FIELD (MISS)
 STATE POT: P 101 BOPD, 38% WTR, CHEST 6084-6115
 4PT COF: 3,437,000 CFGPD, MRW 5642-48
 API #15-189-20,012

S-T-R 13-32S-35W
 SPOT 25' E/C NW SE
 CO STEVENS, KS.
 ELEV 2987 KB

SPUD 10-18-67 8" 1754/700 SX GEOL - PAUL GODOWIC
 DST #1 (U/MRW) 5566-5670, OP NA, GTS/2', MAX GA 5,020,000
 CFGPD, R 360' GCM, ISIP 1650#/30', FP 930-960#, FSIP
 1620#/30'
 DST #2 (CHEST) 6056-6130, OP 5' (PRE FLO) OP 90", WB/20",
 DIED, BY PASSED IN 20", R 170' SOCGCM, NW, ISIP 1781#/30"
 FP 41-103#, FSIP 569#/30" & BLDG

KB LOG TOPS
 HB 4182 -1195
 LAN 4239 -1252
 MAR 4976 -1989
 CHER 5179 -2192
 MRW 5596 -2609
 CHES 5856 -2869
 STE GEN 6128 -3141
 ST L 6190 -3203
 SPERG 6456 -3469
 LTD 6495 -3508

SPL DESC
 ZONE (ST L) 6220-60 VSSO IN FRAC'D LM
 ZONE (ST L) 6297-6308, OOL, BIOCLASTIC LIMESTONE W/TR
 INTER - OOLITIC PORO, W/DARK HEAVY STAIN, SLI OC, &
 FLOURESENT
 DST #3 (ST L) 6210-6330, OP 10" (PRE FLO) WB, DIED IN 30"
 OP NT, NO BLOW ON 2ND OPENING, FLUSHED IN 10" - NO BLOW
 R 45' DM, NSO, ISIP 356#/30", FP 33-40#, FSIP 133#/45"

KB SPL TOPS
 MRW NA
 CHEST 5925
 STE G 6123
 ST L 6205
 RTD 6500-3513

Petroleum Information

WC STEVENS AIKMAN BROS. CORP -
 13-32S-35W #1-A LARRABEE (TWIN)
 25' E OF
 C NW SE

RTD 6500 LOG, 4 1/2" 6221/225 SX
 MICT, CO, GRN LOG, PF 4/6084-86, 30/6100-6115 (CHEST)
 1000/A + 14 BALL SEALERS, \$ 2 BOPH W/GSG, FRAC 30,000 GAL
 JELL 5% A + 27,000# SD + 3000# GLASS BEADS (LD = 850 BBLs)
 RAN TBG W/PKR TO 6060, \$ 250 BL/11 HRS, \$ 118 BF/10 HRS
 (=70% OIL - 30% LD) PULL TBG, PF 12/5642-48 (MRW) PKR 6075
 KILLED W/100 BSW, PKR 5620, \$ 2 BBLs GCM, 750/A (15% BDA)
 LD = 40 BBLs, \$ LD, KICKED OFF & FLO, FLO 1,500,000 CFGPD
 AFTER 11 HRS, FTP 50#, FLO 1,800,000 CFGPD/6 HRS, FTP 75#,
 SI 12 HRS, OPEN WELL & FLO 2,100,000 CFGPD/6 HRS, TP 75#
 KILLED WELL - PULL TBG, FRAC W/15,000 GAL JELL SW + 15,000#
 (LD = 565 BBLs) RAN TBG W/PROD PKR @ 6075, \$ 150 BLW, KICKED
 OFF & FLO, FCP 800#, FLO (TBG) GAS TWTM, CP 325#,
 STATE POT: P 101 BOPD, 38% WTR, CHEST 6084-6115,
 4PT COF 3,437,000 CFGPD, SICP 1395#, MRW 5642-48 COMPLETED 1-11-68
 DUAL COMPLETED (MRW GAS - CHES OIL)

MISC DATA	GEOL	PAUL GODOWIC	ELEV	SPUD DATE	10-18-67
	FTG			DRLG COMP	
	SUPPT	MOBIL OIL CO. FARMOUT		FR by DATA	10-24-67
	CSG	8" 1754/700 SX 4 1/2" 6221/225 SX		COMP by "	1-18-68